



Bid Notice Abstract

Request for Quotation (RFQ)

Reference Number 8778016
Procuring Entity DEVELOPMENT ACADEMY OF THE PHILIPPINES
Title 1 Lot Supply of Supervision, Labor, Materials and Equipment For the Installation of One (1) unit 3TR ceiling cassette Type Inverter Unit of Air-conditioning with BMS ready
Area of Delivery Metro Manila

Solicitation Number:	401113	Status	Pending
Trade Agreement:	Implementing Rules and Regulations	Associated Components	1
Procurement Mode:	Negotiated Procurement - Small Value Procurement (Sec. 53.9)	Bid Supplements	0
Classification:	Goods	Document Request List	0
Category:	Airconditioning and Airconditioning Systems	Date Published	23/06/2022
Approved Budget for the Contract:	PHP 250,000.00	Last Updated / Time	22/06/2022 13:26 PM
Delivery Period:		Closing Date / Time	27/06/2022 10:00 AM
Client Agency:			
Contact Person:	ALVIN PACULA MAGTANGOB BUYER 1 San Miguel Ave., Pasig City Metro Manila Philippines 1600 63-2-63-02-6310921 magtangoba@dap.edu.ph		

Description

1 Lot Supply of Supervision, Labor, Materials and Equipment For the Installation of One (1) unit 3TR ceiling cassette Type Inverter Unit of Air-conditioning with BMS ready Including refrigerant piping, insulation electrical wires And breakers and all other necessary tools and accessories To complete with testing and commissioning at Kennedy Room 3F/B.

A. GENERAL INFORMATION:

- Supply of technical expertise for the provision of detailed work plan;
- Prepare and submit new air-con unit's operation manuals;
- Supervision, Labor, Tools, materials and Equipment for the Installation: Supply of Supervision, Labor, Materials and Equipment For the Installation of One (1) unit 3TR Ceiling Cassette Type Inverter Unit of Air-conditioning with BMS ready Including refrigerant piping, insulation electrical wires And breakers and all other necessary tools and accessories To complete with testing and commissioning at 3B Kennedy room.
- Testing, Cleaning, Clearing, Hauling and Turn-over to include all works but not limited to restoration of all affected facilities, areas, fixtures, etc. due to air-con installation works: and,
- Provision of Post-Installation Documents including Certificate of Warranty to DAP (End User) of at least One (1) year from the date of receipt of Certificate of Completion and Acceptance.

B. SCOPE OF WORK

- Conduct Site Inspection for validation of measurement and linear meter of drainpipes and fill-up Site Inspection form provided by DAP Engineering Unit;
- Supply, Installation and Commissioning of One (1) unit 3TR Ceiling Cassette Type Inverter unit of Air-Conditioning with bms ready at 3B Floor, Kennedy room.
- Delivery the brand new one (1) 3TR ceiling cassette type inverter unit of Air-conditioning with bms ready;

Specification of AC;

a. Voltage/Hz/Phase: 220-240V, 50/60Hz, 1 Phase

b. Cooling: at least 36,000(BTU/Hr)

c. Power Input: at least 2900 (W)

d. BMS Ready

e. EER: at least 3.24

f. Refrigerant: R410A

- Install the ceiling cassette type inverter AC on the ceiling of Kennedy room including refrigerant piping, insulation electrical wires and breakers and all other necessary tools and accessories.
- Install the drain pipes for water leak;
- Testing, Cleaning, Clearing, and Turn-over:
 - Restore to its original condition all affected facilities, areas, fixtures, etc. due to aircon installation works.
 - Clean the areas before turn-over; and,
 - Turn-over the entire project for Acceptance to DAP Engineering Office.
- Provision of Post Installation Documents:

Created by ALVIN PACULA MAGTANGOB

Date Created 22/06/2022

The PhilGEPS team is not responsible for any typographical errors or misinformation presented in the system. PhilGEPS only displays information provided for by its clients, and any queries regarding the postings should be directed to the contact person/s of the concerned party.