



Bid Notice Abstract

Request for Quotation (RFQ)

Reference Number 9094684
Procuring Entity DEVELOPMENT ACADEMY OF THE PHILIPPINES
Title 1 Lot Supply, Installation and Commissioning of New One (1) Unit 1.0HP Inverter-type, Split-type Wall Mounted AC Unit , BMS Ready.
Area of Delivery Metro Manila

Solicitation Number: 403059	Status	Pending
Trade Agreement: Implementing Rules and Regulations		
Procurement Mode: Negotiated Procurement - Small Value Procurement (Sec. 53.9)	Associated Components	1
Classification: Goods	Bid Supplements	0
Category: Airconditioning and Airconditioning Systems	Document Request List	0
Approved Budget for the Contract: PHP 90,000.00	Date Published	10/10/2022
Delivery Period:		
Client Agency:	Last Updated / Time	07/10/2022 15:13 PM
Contact Person: ALVIN PACULA MAGTANGOB BUYER 1 San Miguel Ave., Pasig City Metro Manila Philippines 1600 63-2-63-02-6310921 magtangoba@dap.edu.ph	Closing Date / Time	13/10/2022 10:00 AM

Description

A. GENERAL INFORMATION:

- Supply of Technical Expertise for the provision of Detailed Work Plans;
- Prepare and Submit Duly signed/approved "As-Built Plans" including Brand New Aircon Units operation Manuals;
- Supervision, Labor, Tools, Materials and all other-related items for the:
 - Supply ,Installation and Commissioning of 1-unit Inverter-type, 1.0HP Split-type Wall Mounted A/C to include installation of drain pipes, electrical feeder line, refrigerant pipe, breaker and all other related accessories at PDC office , 5F/A.
 - Testing, Cleaning, Clearing, Hauling and Turn-over to include all works but not limited to restoration of all affected facilities, areas, fixtures, etc. due to aircon installation works; and
 - Provision of Post-Installation Documents including Certificate of Warranty to DAP (End-User) of at least One (1) Year from the date of receipt of Certificate of Completion and Acceptance.

B. SCOPE OF WORK:

- Supply ,Installation and Commissioning of 1-unit Inverter-type, 1.0HP Split-type Wall Mounted A/C to include installation of drain pipes, electrical feeder line, refrigerant pipe, breaker and all other related accessories at PDC Office, 5F/A.

a. Deliver the Brand new One (1) unit Inverter Type, Split-type wall mounted A/C .

Specification:

1. Power Supply: Single Phase 230V, 602Hz
2. Function: Cool/Fan/Dry:
3. Capacity: 1.0HP
4. Power input: 750W
5. Running Current: 4.5A
6. BMS Ready
7. With Remote control

- b. Install drain pipes, Electrical Feeder line, breaker and all other related accessories.
- c. Install the outdoor unit at the specified location and provide all necessary materials;
- d. Test-Run and commissioning the Unit.

- Testing, Cleaning, Clearing and Turn-over;
 - a. Restore To its original condition all affected facilities, areas, fixtures, etc. due to aircon installation works;
 - b. Clean the areas before turn-over; and
 - c. Turn-over the entire project for acceptance to DAP Engineering Office.
- Provision of Post Installation Document:

Submit the following documents for final acceptance to DAP Engineering Office.

- a. Original Copy of "Record drawings/Plan" complete with Legend, Technical Specifications, Test results and measurements; and
 - b. Certification from the contractor specifying warranty of at least one (1) year from the date of receipt of Certification and acceptance; and
 - c. Project duration should be thirty (30) calendar days from the date purchase order is confirmed by the contractor.
- Other Requirements:
 - a. All work-details, Plans, Lay-outs, and schedule should be submitted and approved by the DAP Engineering office before the Contractor begins to Works; and
 - b. Submit hard copy and Soft Copy of before on-going and after pictures.

Created by ALVIN PACULA MAGTANGOB

Date Created 07/10/2022

The PhilGEPS team is not responsible for any typographical errors or misinformation presented in the system. PhilGEPS only displays information provided for by its clients, and any queries regarding the postings should be directed to the contact person/s of the concerned party.