



Bid Notice Abstract

Request for Quotation (RFQ)

Reference Number 9694159
Procuring Entity DEVELOPMENT ACADEMY OF THE PHILIPPINES
Title One (1) Lot Supply of Services, Manpower, Materials, Tools, Equipment, and Other Consumables for the Repainting of the Auditorium Stage Wall and Side Wall Panels At DAPCC in Tagaytay.
Area of Delivery Cavite

| | | | |
|--|---|------------------------------|---------------------|
| Solicitation Number: | 406092 | Status | Pending |
| Trade Agreement: | Implementing Rules and Regulations | | |
| Procurement Mode: | Negotiated Procurement - Small Value Procurement (Sec. 53.9) | Associated Components | 1 |
| Classification: | Goods | Bid Supplements | 0 |
| Category: | Services | | |
| Approved Budget for the Contract: | PHP 150,000.00 | Document Request List | 0 |
| Delivery Period: | | | |
| Client Agency: | | Date Published | 26/04/2023 |
| Contact Person: | ALVIN PACULA MAGTANGOB BUYER 1 San Miguel Ave., Pasig City Metro Manila Philippines 1600 63-2-63-02-6310921 magtangoba@dap.edu.ph | Last Updated / Time | 25/04/2023 16:46 PM |
| | | Closing Date / Time | 02/05/2023 01:00 AM |

Description

A. GENERAL SCOPE OF WORK:

1. Conduct site inspection in order to completely assess the actual condition of the area;
2. Mobilization of all the needed tools, equipment, supplies, machineries and materials on-site including all applicable Personal Protective Equipment (PPE) necessary for the completion of the project;
3. Repainting of Auditorium Stage Wall:
 - Remove any protruding nail, staple, or any sharp material found on the Auditorium Stage Wall;
 - Scrape off all loose, flaking, and peeling paint and other foreign material manually or by using scrapers or paint remover as necessary;
 - Clean/Wash surfaces of side wall panels;
 - Application of material filler for all holes, punctures, or damage found on the Auditorium Stage Wall;
 - Application of Flat Latex White Paint, in two (2) coats. Terminate coating with a clear line without a coating overlap. Paint Swatch shall be approved by DAPCC Management prior to application.
 - Re-coat unsatisfactory finishes. Refinish entire area to corners or other natural terminations.
4. Repainting Of Auditorium Side Wall Panels:
 - Removal of existing cloth installed on the side wall panels;
 - Remove any protruding nail, staple, or any sharp material found on the Side Wall Panels;
 - Scrape off all loose, flaking, and peeling paint and other foreign material manually or by using scrapers or paint remover as necessary;
 - Clean/Wash surfaces of side wall panels;
 - Application of material filler for all holes, punctures, or damage found on the Side Wall Panels;
 - Application of Flat Latex White Paint, in two (2) coats. Terminate coating with a clear line without a coating overlap. Paint Swatch shall be approved by DAPCC Management prior to application.
 - Re-coat unsatisfactory finishes. Refinish entire area to corners or other natural terminations.

5. Proper disposal of the debris out of the DAPCC Premises, shall be the sole responsibility of the awarded supplier;
6. Clearing, Hauling and Disposal of debris that were the result of the implementation of the project. proper disposal of the debris out of the DAPCC Premises, shall the sole responsibility of the contractors;
7. Repair/Repaint/Retouch/Restoration of all DAPCC facility/property that may be damage during the project implementation at the expense of the contractor;
8. Turnover and Acceptance Phase:
 - The contractor shall turnover the completed project for acceptance of the End User and the DAPCC Representative;
 - The supplier shall secure a certificate of service rendered and certificate of completion from End User and the DAPCC Representative.

B. MINIMUM TECHNICAL SPECIFICATION:

I. PAINTING MATERIALS:

1. Compatibility: Materials shall be compatible with one another and the substrates indicated under conditions of service and application. As indicated on the manufacturer's brochure and materials safety data sheet.
2. Mixing and Tinting:
 - All paint Shall be ready-mixed and pre-tinted. All paint materials prior to and during application shall be done so as to ensure the uniform, color, and consistent finish.
 - Paint Thinner addition shall not exceed the manufacturer's brochure recommendations. Do not use kerosene or other organic solvents to thin water based paint.
3. Flat White , Acrylic Latex Paint: 100% acrylic latex "odor-less" paint with excellent hiding, and durability. For interior and exterior surfaces such as concrete, hollow blocks, and drywall surfaces.

II. WORKMANSHIP:

1. All work shall be done by skilled painters, either by brushing or spraying on the surface as required. All paints shall be evenly applied so as to be free from sags, runs, crawls, or other defects. All coats shall have minimum brush marks. All brushes to used shall be clean and in good condition.
2. All paints shall be thoroughly stirred so as to keep the pigment evenly in suspension when paint is being applied.
3. No painting shall be done in damp weather or under conditions that unsuitable for the production of good result.
4. All coats shall be thoroughly dry before the succeeding coat is applied, and as specified by the manufacturer.

C. OTHER REQUIREMENTS:

1. Interested contractors must do a site visit at DAPCC before submitting a proposal/quotation;
2. The Contractor must clearly itemize the cost components of the Quotation, to include data as follows:
 - All materials/equipment/parts/items to be used shall include its specifications. No change specifications of the materials will be entertained unless the change is approved in writing; and
 - For Labor / Technical Supervision: Specify labor type and amount.
3. All work-details, plans, lay-outs, and schedule should be submitted in the form of Permit to Work issued by DAPCC Engineering Office and endorsed by the EMS Manger and approved by the Department Manager of DAPCC. DAPCC Work Permit shall be secured at least three (3) days prior to project implementation;
4. All necessary and applicable permits and licenses shall be secured by the contractor;
5. Ensure visibility and presence of safety signages/barricades/barriers in all areas affected;
6. Ensure the safety and security of all DAPCC guests, clients, personnel and properties in the performance of the activities;
7. Provision of first aid tools, supplies, and other paraphernalia must be present at all times and should be made available by the contractor to ensure safety of workers and other personnel;
8. The DAPCC shall issue a Certificate of Project Completion once all requirements and activities have been fully met as attachment for the processing of payment; and
9. Protect Duration/Committed Completion Date Should not be later than Fifteen (15) calendar days from the date of receipt of Notice to Proceed or Purchase Order and must be clearly stated in the Final Quotation.

Created by ALVIN PACULA MAGTANGOB

Date Created 25/04/2023

The PhilGEPS team is not responsible for any typographical errors or misinformation presented in the system. PhilGEPS only displays information provided for by its clients, and any queries regarding the postings should be directed to the contact person/s of the concerned party.