



Bid Notice Abstract

Request for Quotation (RFQ)

Reference Number 9711500
Procuring Entity DEVELOPMENT ACADEMY OF THE PHILIPPINES
Title One (1) Lot Supply of Services, Materials, Manpower, Tools, Equipment, Delivery, and Installation for the Repair, Refurbishing, Restoration of DAP Corporate Logos at the DAP Conference Center in Tagay
Area of Delivery Cavite

| | | | |
|--|---|------------------------------|---------------------|
| Solicitation Number: | 406120 | Status | Pending |
| Trade Agreement: | Implementing Rules and Regulations | Associated Components | 1 |
| Procurement Mode: | Negotiated Procurement - Small Value Procurement (Sec. 53.9) | Bid Supplements | 0 |
| Classification: | Goods | Document Request List | 0 |
| Category: | Signage and Accessories | Date Published | 03/05/2023 |
| Approved Budget for the Contract: | PHP 78,000.00 | Last Updated / Time | 02/05/2023 13:26 PM |
| Delivery Period: | | Closing Date / Time | 08/05/2023 01:00 AM |
| Client Agency: | | | |
| Contact Person: | ALVIN PACULA MAGTANGOB BUYER 1 San Miguel Ave., Pasig City Metro Manila Philippines 1600 63-2-63-02-6310921 magtangoba@dap.edu.ph | | |

Description

PROJECT COMPONENT NO. 1:
"The DAP Corporate Logo at Gate 1 along Isaac O. Tolentino Avenue"

PROJECT COMPONENT NO. 2:
"The DAP Corporate Logo at the Facade Wall of the Auditorium"

A. GENERAL SCOPE OF WORK:

1. Conduct site inspection in order to completely assess the actual condition of the working area;
2. Mobilization of all the needed tools, equipment, supplies, machineries and materials on-site including all applicable Personal Protective Equipment (PPE) necessary for the completion of the project;
3. Provide manpower during project implementation until completion;
4. Ensure the safety and security of all DAP personnel and properties during the implementation of the activities;
5. Repair/repair /retouch/restore DAP property that may be damaged as a result of the works during the project implementation at the expense of the contractor;
6. Ensure visibility and presence of safety signages/barricades/barriers in all areas affected;
7. Proper disposal of the debris out of the DAPCC Premises, shall be the sole responsibility of the awarded supplier;
8. Clearing, Hauling and Disposal of debris that were the result of the implementation of the project. Proper disposal of the debris out of the DAPCC Premises, shall be the sole responsibility of the contractor;

B. SPECIFIC SCOPE OF WORK:

I. PROJECT COMPONENT NO. 1

- a.) Dismantling of Frame including Hauling/transportation along with proper safekeeping of the DAP Logo and letters are included;

- b.) Fabrication of new housing/framing including background of the signage with protective acrylic panels;
- c.) Installation of back lights (LED) per individual letter and for the logo;
- d.) The original brass logo and letters will be retained/reuse. Inclusive of the polishing and buffing of the brass logo and letters;
- e.) Dimensions: Length: 421 cm, Height: 142cm, Thickness: 20 cm;
- f.) The original lay-out of the logo and letters will remain the same.
- g.) Overall output will look similar to the original design only with new housing materials, installed acrylic panels and installment of LED Back light; and
- h.) Delivery and Installation of refurbished DAP Corporate Logo, inclusive of housing/framing including background of the signage with protective acrylic panels.

II. PROJECTCOMPONENTNO. 2:

- a.) Scaffolding erection along with platforms and ladders, in front of the auditorium facade wall where the logo is located;
- b.) Removal of the blue back ground;
- c. Cleaning of surface of the wall that will be exposed from the removal of blue background to blend with the existing facade;
- d. Application of new paint, including surface preparation, for the part of the wall that was covered by the brass logo;
- e.) Removal of the logo and letters;
- f.) Re-polishing and buffing of the brass logo and letters
- g.) Installation of the brass logo and letters in the same lay-out and same position as it was previously installed; and
- h.) Repair of the chipped/damaged cement due to the removal of blue background and installation of the brass material.

C. OTHER REQUIREMENTS:

1. Submit Covid-1g vaccination with at least One (1) booster shot of all manpower shall be presented prior to entry at DAPCC premises;
2. Interested contractors are encouraged to do site visit at DAPCC before submitting a proposal/quotation;
3. Implementation of the project shall be subject to the availability and clearance of the DAPCC Management;
4. All necessary and applicable permits and licenses shall be secured by the contractor;
5. DAPCC Work Permit shall be secured at least one (1) day prior to project implementation;
6. Provision of first aid tools, supplies, and materials must be present at all times and should be provided by the contractor;
7. The Contractor shall issue a Certificate of Warranty reflecting the validity of at least six (6) months from the date that is was accepted by the DAPCC;
8. The DAPCC shall issue a Certificate of Project Completion once all requirements and activities have been fully met as attachment for the processing of payment;
9. PROJECT DURATION/COMMITTED COMPLETION DATE should not be later than Thirty (30) calendar days from the date of receipt of Notice to Proceed or Purchase Order and must be clearly stated in the Final Quotation;

Created by ALVIN PACULA MAGTANGOB

Date Created 02/05/2023

The PhilGEPS team is not responsible for any typographical errors or misinformation presented in the system. PhilGEPS only displays information provided for by its clients, and any queries regarding the postings should be directed to the contact person/s of the concerned party.