BID BULLETIN No.1

20 October 2023 (Friday)

BIDDING NO.:	Title/Description:
IB23-408235-04	"ONE (1) LOT SUPPLY, DELIVERY,
APPROVED BUDGET CEILING (ABC):	INSTALLATION, CONFIGURATION, TESTING
₱3,500,000. <u>⁰⁰</u>	& COMMISSIONING, AND UPGRADING OF
Date of Pre Bid Conference	THE CLOSED-CIRCUIT TELEVISION
10 October 2023 (Tuesday); 10:00 AM	SURVEILLANCE SYSTEM AT DAP
Via Google Meet Platform	
meet.google.com/uun-xyfm-ssr	CONFERENCE CENTER IN TAGAYTAY"

Relative to the conducted Pre-Bid Conference via Google Meet for the above-stated Project last October 10, 2023 (Tuesday) and the conducted site visit last October 12-13, 2023, the following clarifications from prospective bidders are being posted for the information of all concerned, as approved by the BAC & TWG:

References based on the OBD / Pre- Bid Conference / Site Inspection	Description based on the OBD / Queries	New description / Clarification
OBD page 26, item No.1.01 of (Section VII. Technical Specifications) Supply and installation of Dome IP CCTV Camera	•4MP (1920 x 1080) @30 fps, 1/2.9"" image sensor •24/7 Full-color image, starlight, WDR •SMART H.264+/H.265+ •2.8/3.6 mm fixed lens •Built-in warm light/IR LED, the max. illumination distance is 30 m and the max. warm light distance is 10m •Intelligent monitoring: Intrusion, tripwire (the two functions support the classification and accurate detection of vehicle and human). •12V DC/PoE power supply •IP67 protection •with Warranty	•1/3 in. 4MP Progressive-scan CMOS Sensor •Triple-stream Encoding •Smart H.265+ and Smart H.264+ Dual Codec •4MP (2688 × 1520) @30 fps, 2.8, Fixed Lens •Starlight Technology for Lowlight Applications •Analytics+ Function – Perimeter Protection and Smart Motion Detection •True Wide Dynamic Range (120 dB) and Day/Night IR Cut Filter •Enhanced Power and Data Transmission Distances (ePoE) •Arctic Pro Series Camera – Operational down to -40deg C(-40deg F) •IP67 Ingress Protection and IK10 Vandal Resistance •with Warranty
OBD page 27-28, item No.1.05 of (Section VII.	Specification: Supply and installation of Data Cabinet	Specification: Supply and installation of Data Cabinet

20 October 2023 (Friday)

p.2/13

References based on the OBD / Pre-Bid Conference / Site Inspection	Description based on the OBD / Queries	New description / Clarification
Technical Specifications) Data Cabinet	•Data Cabinet with a minimum specification of at least: Can accommodate at least four (4) and two (2) Data Switches each; •(9U & 12U) 19" standard opening; Framing and Paneling Gauge#16, Black (powdercoated); Adjustable with mounting railings; Plexiglas Front Door with Lock; •Detachable Side Panels with Lock & Ventilation; Detachable Back Panels with Lock; With 1 unit Vertical powerstrip 4 CO's, 3 prong, 220V, 20 Amp fuse; With 1 unit Vertical Cable Manager at the back ring type; and with 2 pcs. Exhaust Fan at the top panel •with Warranty	 Data Cabinet will be installed in the following areas: PABX Room (28U / 4 feet Data Cabinet); Workshop Electrical Room (9U / 1.5 feet Data Cabinet); Electrical Room at RFS Office (9U / 1.5 feet Data Cabinet); and Basement Electrical Room (12U / 2 feet Data Cabinet) (9U, 12U, & 28U) 19" standard opening; Framing and Paneling Gauge#16, Black (powder-coated); Adjustable with mounting railings; Plexiglas Front Door with Lock; Detachable Side Panels with Lock & Ventilation; Detachable Back Panels with Lock; With 1-unit Vertical powerstrip 4 CO's, 3 prong, 220V, 20 Amp fuse; With 1-unit Vertical Cable Manager at the back-ring type; and with 4 pcs. Exhaust Fan at the top panel with Warranty Kindly refer to Annex "A"-Revised Section VII: Technical Specifications and Annex "B"-Revised Form 2: Price Schedule, and

References based on the OBD / Pre-Bid Conference / Site Inspection	Description based on the OBD / Queries	New description / Clarification
		Annex "C" Schedule of Requirements.
OBD page 27, item No. 1.03 of (Section VII. Technical Specifications) Smart POE Unmanaged Data Switch	•Specification: •Smart POE Unmanaged Data Switch (The next generation Smart switch, provides 48 ports – 48 10/100/1000 Base-T POE ports, support IEEE 802.3af/ at power supply standard, single port maximum output PoE power 30W, 370W max output PoE power, support unified/centralized management, lifetime license); •Combo PoE Switch •Interface: Combo 1000 Base-T/SFP port x 110/100 Base-T x16 (Hi PoE/PoE+/PoE) PoE budget: 135 W Dimension: 340 mm x 200 mm x 43 mm CCTV monitor mode, VLAN isolation mode •with Warranty	Specification: Smart POE Unmanaged Data Switch (The next generation Smart switch, provides 24 ports – 24 10/100/1000 Base-T POE ports, support IEEE 802.3af/ at power supply standard, single port maximum output PoE power 30W, 370W max output PoE power 30W, 370W max output PoE power, support unified/centralized management, lifetime license); Combo PoE Switch Interface: Combo 1000 Base-T /SFP port x 110/100 Base-T x16 (Hi PoE/PoE+/PoE) PoE budget: 135 W Dimension: 340 mm x 200 mm x 43 mm CCTV monitor mode, VLAN isolation mode with Warranty
OBD page 34, item No.1.57 of (Section VII. Technical Specifications)	Description: •End to End Termination, Testing including Fluke testing and Optimal Time-Domain Reflectometer (OTDR) & Commissioning, Fiber Optics, Networking, Fiber Optic Cable Design, and Installation, Fiber Termination and Fusion Splicing (FOC Fusion Machine), FOC Patch Panel	Description; •End to End Termination, Testing including Fluke testing and Optimal Time-Domain Reflectometer (OTDR) & Commissioning, Fiber Optics, Networking, Fiber Optic Cable Design, and Installation, Fiber Termination and Fusion Splicing (FOC Fusion Machine), FOC Patch Panel



on the OBD / Pre- Bid Conference / Site Inspection	Description based on the OBD / Queries	New description / Clarification
	Splicing, and Termination, Continuity Testing Power source and Light Meters Configuration, Installation / termination and adjustment, and Programming, for the entire IP CCTV system;	Splicing, and Termination, Continuity Testing Power source and Light Meters Configuration, Installation/termination and adjustment, and Programming, Decommissioning and Turnover of all identified obsolete CCTV Cameras, Cablings, and other accessories, and system integration and configuration of existing CCTV System at Cottages (via internet/data connection) for the entire IP CCTV system. •Repair of three (3) identified CCTV units at Cottages. •Supply and installation of 4+2 100 Mbps Long-Range PoE Switch (Model: WI-PS205H).
OBD page 29 Item 1.12 (Section VII. Technical Specifications) UTP CAT6 Cable	Specification: •Supply & Installation of UTP CAT6 Cable; •with Warranty	Specification:
Site Inspection	Request/Follow-up: Detailed Floor Plan that includes the following:	TWG Reply: Kindly refer to Annex "A"- Revised Section VII:

References based on the OBD / Pre-Bid Conference / Site Inspection	Description based on the OBD / Queries	New description / Clarification
	-with plotting of cable tray or desired location on where the cable tray to be layout in your premises -with detailed dimension and exact location of existing camera with label or numbering that to be upgraded and additional IP Camera -clear copy -pdf format	and Annex "B"-Revised Form 2: Price Schedule for the requested floor plans, CCTV locations, view, and cable tray layout, including the Proposed Single Line Diagram for the CCTV Surveillance System
Site Inspection	Query:	TWG Reply:
	Is this project subject for PEZA application? -Electronics Permit -Permit-to-install	The project aims to install a new electronic system, particularly to CCTV Surveillance System. It is a must to have all necessary permits that may be required by other oversight agencies such as Local Government Units (LGUs). All necessary permits that may be required by this transaction must be secured by the winning bidder.
Site Inspection	Query:	TWG Reply:
	For cable tray structure,	For cable tray structure,
	-Is a cable tray a fully enclosed or perforated type of cable tray?	-Fully enclosed. The Cable Tray must be the same as the cable tray installed at the Dormitory Building for the Access Points Project.
	-Is this galvanized or powdered coated only?	-The cable must be Powdered coated.

References based on the OBD / Pre- Bid Conference / Site Inspection	Description based on the OBD / Queries	New description / Clarification
	-If powdered coated, what is the preferred color?	-The preferred Color for the cable tray is gray.
	-What is the dimension of the cable tray or wireways?	-Dimensions of the Cable Tray or wire ways are the following: Height: two (2) inches; Width: six (6) inches; Length: three (3) meters.
Site Inspection	Query:	TWG Reply:
	What type of conduit to be used to embed that passing or crossing along the road and perimeter going to the nearest data cabinet?	PVC Orange Conduit Pipes (Schedule 80) may be used to embed that passing or crossing the road (Dormitory Building to Engineering Building), and perimeter (Gate 2) going to the nearest data cabinet.
Site Inspection	Query:	TWG Reply:
	Camera #57 & 58 (additional) at the Perimeter, where is the location of Data Cabinet that will link the camera #57, and 58?	Cabinet that will link the
Site Inspection	Agreement:	TWG Reply:
	That we allow us to used PVC pipe and plastic molding for the layout.	PVC Pipes are used to distribute UTP Cables from the Cable Tray to the respective CCTV Camera Locations. The use of plastic molding maybe permitted at areas/locations which needs to consider the aesthetic condition when it will be installed in that particular area/locations. Such areas may be at Upper Lobby, Conference Hallways, Workshop Hallways, etc.

References based on the OBD / Pre-**Description based on the New description / Bid Conference / OBD / Queries** Clarification Site Inspection That we allow us to mount the This is noted. Kindly include the weatherproof boxes to be perimeter camera to your Street Light with Pole. mounted for each perimeter camera that would mounted to the Street Light with Pole. Site Inspection Request: TWG Reply: We would like to request an Kindly refer to Annex "A"-Revised original or clear copy of the file: Section VII: Technical **Specifications** 1) Proposed **CCTV** "B"-Revised and Annex location. view. and Form 2: Price Schedule for number the requested floor plans, **CCTV** 2) Proposed CCTV locations, view, and Surveillance System cable tray layout, including the Layout with dimensions **Proposed** Single Line on floor plan Diagram for the **CCTV** Surveillance System 3) Floor Plan with cable tray layout OBD page 30, item **Specification: Specification:** No.1.19 of (Section Installation of Data Cabinet with Installation of Data Cabinet with height 28U / 4 ft., Powder height 12U / 2 ft., Powder Technical VII. Specifications) Area Coated, Black, perforated two Coated, Black, perforated two side panels, Perforated back, side panels, Perforated back. (Data Cabinet and front Door; German cooling Installation front Door; German at PABX Room) fan, with three pins German cooling fan, with three pins type plug, 1wire,4 fans (cable German type plug, 1wire,4 fans (cable length, 1M); 1U length, 1M); 1U 19" power Site Inspection distribution unit, w/ aluminum 19" power distribution unit, w/ body, US (NEMA5-15P) Plug, 6 aluminum body, US (NEMA5universal outlets, w/LED master 15P) Plug, 6 universal outlets, switch at PABX Room: w/LED master switch at PABX Room. OBD page 30, item **Specification: Specification:** Installation of One (1) unit No.1.27 of (Section Installation of One (1) unit Data Cabinet with specifications of with Technical Data Cabinet 600 x 450, 9u/1.5Ft. 90.7kg specifications of 600 x 450. Specifications) Area (Data 9u/1.5Ft. 90.7kg max. loading Cabinet max. loading capacity), Installation toughed glass door w/ spring capacity), toughed glass door



References based on the OBD / Pre-Bid Conference / Site Inspection	Description based on the OBD / Queries	New description / Clarification
Electrical room located at the RFS Office)	lock, detachable side panel (not vented), 2 pcs. Exhaust fan w/cable entry at the top panel, 6 outlet PDU w/ 3.0mm cable length (220V,3prong,10A), powder coated finish, with exhaust fans at the Electrical room located at the RFS Office area;	w/ spring lock, detachable side panel (not vented), 2 pcs. Exhaust fan w/ cable entry at the top panel, 6 outlet PDU w/ 3.0mm cable length (220V,3prong,10A), powder coated finish, with exhaust fans at the Electrical room located at the RFS Office area; with provision of 1KVA UPS Floor/Wall Mount (4x Universal Outlets, Cable Length: 1.20 meters, Rated Power: 600 Watts, Height x Width x Depth: 9.25 x 16.05 x 30.5 cm
OBD page 30, item No.1.28 of (Section VII. Technical Specifications) Area 1 (Data Cabinet Installation at Electrical room located at the RFS Office)	Specification: Installation, testing, and commissioning of Two (2) Smart PoE Managed Switch to the Data Cabinet	Specification: Installation, testing, and commissioning of One (1) Smart PoE Managed Switch to the Data Cabinet
OBD page 31, item No.1.28 of (Section VII. Technical Specifications) Area 1 (Data Cabinet Installation at Electrical room located at the Workshop Area)		Specification: Installation, testing, and commissioning of One (1) Smart PoE Managed Switch to the Data Cabinet
OBD page 31, item No.1.30 of (Section VII. Technical Specifications) Area 1 (Data Cabinet Installation at	Specification: Installation of One (1) unit Data Cabinet with specifications of 600 x 450, 9u/1.5Ft. 90.7kg max. loading capacity), toughed glass door w/ spring	Specification: Installation of One (1) unit Data Cabinet with specifications of 600 x 450, 9u/1.5Ft. 90.7kg max. loading capacity), toughed glass door

References based on the OBD / Pre-Bid Conference / Site Inspection	Description based on the OBD / Queries	New description / Clarification
Electrical room located at the Workshop Area)	lock, detachable side panel (not vented), 2 pcs. Exhaust fan w/ cable entry at the top panel, 6 outlet PDU w/ 3.0mm cable length (220V,3prong,10A), powder coated finish, with exhaust fans at the Electrical room located at the RFS Office area;	w/ spring lock, detachable side panel (not vented), 2 pcs. Exhaust fan w/ cable entry at the top panel, 6 outlet PDU w/ 3.0mm cable length (220V,3prong,10A), powder coated finish, with exhaust fans at the Electrical room located at the Workshop Area; with provision of 1KVA UPS Floor/Wall Mount (4x Universal Outlets, Cable Length: 1.20 meters, Rated Power: 600 Watts, Height x Width x Depth: 9.25 x 16.05 x 30.5 cm
OBD page 27-28, item No.1.05 of (Section VII. Technical Specifications) Data Cabinets	Query: Upon checking of the OBD, there's only three (3) data cabinets included in the OBD. These are installed at PABX Room, Workshop Area, and RFS Office (Electrical Room). Where is the location of fourth data cabinet?	 Specification: Data Cabinet will be installed in the following areas: PABX Room (28U / 4 feet Data Cabinet); Workshop Electrical Room (9U / 1.5 feet Data Cabinet); Electrical Room at RFS Office (9U / 1.5 feet Data Cabinet); and Basement Electrical Room (12U / 2 feet Data Cabinet) (9U, 12U, & 28U) 19" standard opening; Framing and Paneling Gauge#16, Black (powder-coated); Adjustable with mounting railings; Plexiglas Front Door with Lock; Detachable Side Panels with Lock and ventilation;

References based on the OBD / Pre- Bid Conference / Site Inspection	Description based on the OBD / Queries	New description / Clarification
		Detachable Back Panels with Lock; With 1-unit Vertical powerstrip 4 CO's, 3 prong, 220V, 20 Amp fuse; With 1-unit Vertical Cable Manager at the back ring type; and with 4 pcs. Exhaust Fan at the top panel • with Warranty
Pre-Bid Conference	Query during Pre-Bid Conference:	TWG Reply during Pre-Bid Conference:
	If one of the requirements for the project is PCAB License?	BAC EU Rep. Engr. AAMJimenez answered that this project is classified under Goods, therefore there is no need for a PCAB License.
		Note: Under the Revised IRR of RA9184, see Section 23. Eligibility Requirements for the Procurement of Goods and Infrastructure Projects
Pre-Bid Conference	Query during Pre-Bid Conference:	TWG Reply during Pre-Bid Conference:
	For clarification regarding with the Checklist item no. 9 re: Certificate of Distribution and Service, what does it mean?	"The Certificate of Distribution and Service certifies a company as either a Distributor or a Service Provider with the capability to install specific equipment, such as CCTV systems."
Pre-Bid Conference	Query during Pre-Bid Conference:	TWG Reply during Pre-Bid Conference:
	In regards with the Company Profile with the list of clients, do we need to provide the projects that we have done with them?	If you can provide the names of the project, much better for the TWG's reference for verification. If ever it is a bulk,

References based on the OBD / Pre- Bid Conference / Site Inspection	Description based on the OBD / Queries	New description / Clarification
		kindly range it as a simplified list as long as it is related with the project.
Pre-Bid Conference	Query during Pre-Bid Conference:	TWG Reply during Pre-Bid Conference:
	Regarding with the existing units, do we need to care off the dismantling of cablings?	Yes.
Pre-Bid Conference	Query during Pre-Bid Conference:	TWG Reply during Pre-Bid Conference:
	In regards with the item "1.4 UPS Power Supply", which type is your requirement? Is it Rack Type or Tower Type?	Our requirement is Rack Tower Convertible.
Site Inspection	Query:	TWG Reply:
	There are 73 units of CCTV Camera will be subject for replacement, but there are 78 units of CCTV Camera in the Summary of CCTV Locations, Views, and Number. Where is 5 units of CCTV Camera?	Five (5) units of CCTV cameras will be "retained", and these are located, and numbered as follows: 1) Gallery Hallway (#63) 2) Gallery Inside 1 (#64) 3) Gallery Inside 2 (#65) 4) Gallery Inside 3 (#66) 5) PABX (#67)
		Conduit Piping, UTP Cabling Installation (Two Runs per CCTV Camera), and the integration of this camera into the new IP CCTV System are included in this project.

Note: The Specifications are the minimum standards. The Bidders may submit higher or better specifications.



Reminder to Bidders:

- 1. Prospective Bidders may obtain further information from DAP and inspect the Bidding Documents at the address given below from Monday to Friday, **9:00AM to 4:30PM**.
- 2. A complete set of Official Bidding Documents (OBD) may be acquired by interested Bidders until **10 November 2023 (Fri)** from 09:00AM to 04:30PM, of the non-refundable applicable fee for the Bidding Documents, pursuant to the latest Guidelines issued by the GPPB, the cost for the Official Bidding Documents is **THREE THOUSAND FIVE HUNDRED PESOS (P3,500.00)**.

It may also be downloaded free of charge from the website of the Philippine Government Electronic Procurement System (PhilGEPS) and the website of the DAP. In order for bidders to participate, they shall pay the cost of the OBD not later than the scheduled Submission and Opening of the Bids.

3. Interested bidders must make payment to:

Account Name:	Development Academy of the
	Philippines
Account Number:	0671-0105-40
Bank:	Landbank of the Philippines
Branch of Account:	Pasig Capitol Branch

A copy of proof of payment must be emailed to DAP's Finance Department at: cashtreasury@dap.edu.ph for the issuance of Official Receipt (OR) and the BAC Secretariat will provide assistance to the On-line Bidder for the creation of "bidms account" and dedicated site in the bidms.dap.edu.ph.

- 4. In compliance with GPPB Resolution No. 12-2020, all electronic-Bids must be duly received by the Bids and Awards Committee (BAC) Secretariat, through the designated bidms.dap.edu.ph secured account on or before **November 14**, **2023 (Tue)** and not later than **10:00AM**. All bids must be accompanied by a bid security in any of the acceptable forms and in the amount stated in **ITB** Clause 14.
- 5. Bid opening shall be on **November 14, 2023 (Tue)** at **10:00AM** via Google Meet Platform. Electronic bids will be opened in the presence of the bidders' authorized representative/s who are authorized to attend the proceedings. **LATE BIDS SHALL NOT BE ACCEPTED**.
- 6. The **DAP** reserves the right to reject any and all bids, declare a failure of bidding, or not award the contract at any time in accordance with the provisions of RA 9184 and its IRR, without thereby incurring any liability to the affected bidder or bidders.



DATE OF ISSUE

20 October 2023 (Friday)

Page Number **p.13/13**

7. For further information, please refer to:

MARIET RIZ M. BRADECINA

Manager, BAC Secretariat Division (SO-2023-094)

DEVELOPMENT ACADEMY OF THE PHILIPPINES GF DAP Bldg., San Miguel Avenue, Pasig City 1600

P.O. Box 12788 Ortigas Center, Pasig City 1600 Philippines

Telephone No.

BAC Secretariat email
Website address

: (632) 8631-0921 loc. 133
: dapbacsec@dap.edu.ph
: http://www.dap.edu.ph

8. You may visit the following websites:

For downloading of Official Bidding Documents: https://www.dap.edu.ph/invitation-to-bid/
For online bid submission: http://bidms.dap.edu.ph/page/

For the guidance and information of all concerned.

ALAN S. CAJES

CHAIRPERSON, BIDS & AWARDS COMMITTEE 2 (SO No.2023-047)

>>>NOTHING FOLLOWS<<



20 October 2023 (Friday)

DATE OF ISSUE

p.1/28

PAGE NUMBER

Bidder's LETTERHEAD

FORM 10: TECHNICAL SPECIFICATIONS COMPLIANCE

Instructions: Bidders must state here either "Comply" or "Not Comply" against each of the individual parameters of each Specification stating the corresponding performance parameter of the equipment offered. Statements of "Comply" or "Not Comply" must be supported by evidence in a Bidders Bid and cross-referenced to that evidence. Evidence shall be in the form of the manufacturer's un-amended sales literature, unconditional statements of specification and compliance issued by the manufacturer, samples, independent test, data etc., as appropriate. A statement that is not supported by evidence or is subsequently found to be contradicted by the evidence presented will render the Bid under evaluation liable for rejection. A statement either in the Bidder's statement of compliance or the supporting evidence that is found to be false either during Bid evaluation, post-qualification or the execution of the Contract may be regarded as fraudulent and render the Bidder or supplier liable for prosecution.

Item	Specification	Qty	unit	Statement of Compliance
HARDWARES	S			
1.01 Dome IP Camera	Supply and installation of Dome IP CCTV Camera: 1/3 in. 4MP Progressive-scan CMOS Sensor Triple-stream Encoding Smart H.265+ and Smart H.264+ Dual Codec 4MP (2688 × 1520) @30 fps, 2.8, Fixed Lens Starlight Technology for Low-light Applications Analytics+ Function —Perimeter Protection and Smart Motion Detection True Wide Dynamic Range (120 dB) and Day/Night IR Cut Filter Enhanced Power and Data Transmission Distances (ePoE) Arctic Pro Series Camera — Operational down to -40deg C(- 40deg F) IP67 Ingress Protection and IK10 Vandal Resistance with Warranty	52.00	pcs	
1.02 Bullet IP Camera	Supply and installation of Bullet IP CCTV Camera: • 5MP (2592 × 1944) @20 fps, 1/2.7"" image sensor, 24/7 Full-color image • SMART H.264+/H.265+, AI	21.00	pcs	



20 October 2023 (Friday)

DATE OF ISSUE

p.2/28

PAGE NUMBER

(AS PER BID BULLETIN No.1)

H.264/H.265 encoding 2.8/3.6 mm fixed lens · Built-in warm light and IR LED; the max. IR illumination distance is 30m Smart Dual Illumination Active Deterrence: Sound and light alarm Support vehicle and human classification Intelligent detection: Intrusion, tripwire 12V DC/PoE power supply IP67 protection with Warranty Supply and installation of 24 port Smart 1.03 Smart 6.00 POE POE Unmanaged Data Switch: Unmanaged Smart POE Unmanaged Data Switch Data Switch (The next generation Smart switch, provides 24ports 10/100/1000Base-T POE ports, 4SFP optical ports, support IEEE 802.3af/ at power supply standard, single port maximum output PoE power 30W, 370W max output PoE power, support unified/ centralized management, lifetime license); Combo PoE Switch Interface: Combo 1000BASE-T/SFP port x 110/100 Base-T x16 (Hi PoE/PoE+/PoE) PoE budget: 135W Dimension: 340mm x200mm x43mm CCTV monitor mode, VLAN isolation mode with Warranty 1.04 Supply and installation of Two (2) 64 2.00 Channel Network Video Recorder: Channel Network Video Smart H.265+/Smart Recorder H.264+/H.265/H.264 support 64-ch IPC inputs, max resolution 12MP 320Mbps input Bandwidth Support 16-ch 1080p@30 fps selfadaptive decoding ability . 8 SATA III ports, up to 10 TB for a single HDD 2 VGA, 2 HDMI, 2 RJ45(1000M) Supports ONVIF protocol, DHCP, P2P function · 1-channel fisheye dewarping (AI by NVR) Al by Camera: Perimeter protection;



20 October 2023 (Friday)

DATE OF ISSUE

p.3/28

Page Number

	face detection and recognition; SMD			
	Plus; video metadata; ANPR; people			
	counting; heat map			
	with Warranty			
1.05 Data	Supply and installation of Data Cabinet:	4.00	pcs	
Cabinet	Data Cabinet will be install at the			
	following areas:			
	✓ PABX Room (28U / 4 feet Data			
	Cabinet);			
	 ✓ Workshop Electrical Room (9U 			
	/ 1.5 feet Data Cabinet);			
	✓ Electrical Room at RFS Office			
	(9U / 1.5 feet Data Cabinet);			
	and			
	✓ Basement Electrical Room (12U			
	/ 2 feet Data Cabinet)			
	(9U, 12U, & 28U) 19" standard (9U, 12U, & 28U) 19" standard			
	opening; Framing and Paneling			
	Gauge#16, Black (powder-coated);			
	Adjustable with mounting railings; Plexiglas Front Door with Lock;			
	Detachable Side Panels with Lock &			
	Ventilation; Detachable Back Panels			
	with Lock; With 1 unit Vertical			
	powerstrip 4 CO's, 3 prong, 220V, 20			
	Amp fuse; With 1 unit Vertical Cable			
	Manager at the back ring type; and			
	with 4 pcs. Exhaust Fan at the top			
	panel			
	with Warranty			
1.06 10TB	10TB Surveillance Hard Disk Drive	16.00	pcs	
Hard Disk	SATA III;			
Drive	with Warranty			
1.07 Fiber	 LC with Standard Boots; 	1.00	roll	
Patch Cable	 LC 12mm/18mm with Short Boots; 			
End to End	 SC 25mm with Short Boots 			
(300M)	Polish Type SMF: UPC-UPC; UPC-			
	APC; APC-APC; MMF: UPC-UPC			
	Connector Ferrule Zirconia Ceramic			
	Cable Outside Diameter Duplex:			
	1.6/2.0/3.0mm, Simplex:			
	0.9/2.0/3.0mm, Interchangeability			
	≤0.2dB, Vibration ≤0.2dB			
	with Warranty			
1.08 Fiber	 Single mode single fiber; LC port; 	6.00	pcs	
Optical	1310nm sending, and 1550nm			
Module	receiving; Transmission distance up			
	to 20km;			
4.00.55"	with Warranty	0.00		
1.09 55" LED	55" 4K UHD LED Monitor;	2.00	pcs	
4K Monitor	 Industrial level LCD panel, suitable 			



20 October 2023 (Friday)

DATE OF ISSUE

p.4/28

Page Number

	for continuous 24/7 operation 4K Ultra-HD resolution Using tamper-proof metal housing Built-in 3D COMB filter and 3D noise reduction 6ms response time for no motion blur or ghosting 1.07G colors, for a realistic and immersive visual experience High-fidelity digital processing 178°/178° wide uninterrupted viewing angle With Bracket with Warranty			
1.10 Fiber	Category 6 180° 1U 24-Port	6.00	pcs	
Patch Panel	Unshielded Patch Panel, Dual Type IDC, W/ Two Cable Management Bars, Black; with Warranty	5.00	pcs	
1.11 Fiber	LC/UPC - SC/UPC Duplex Single	80.00	pcs	
Patch Cord	mode, • 9/125 Patch Cord 2M,2.0mm, LSOH; • with Warranty			
1.12 UTP CAT6	Supply & Installation of Universal	1	lot	
Cable	Twisted Pair (UTP) Category 6 (CAT 6) Cable, 305 meter or 1000 ft. per box; • with Warranty			
1.13 LC Pigtail	Multimode OM3 Simples 1M, 4.0	25.00	pcs	
	mm, LSOH; with Warranty			
1.14 Smart- UPS Power Supply	 Supply & Installation of High frequency, On-line Smart UPS, Rack-Tower Convertible, Hot-Swappable Battery Module Design, 3KVA/2.7 KW, PF: 0.9, 72Vdc, with 6pcs X 9Ah built-in battery, with USB, RS232, EPO, SNMP function Port with Warranty 	1.00	pc	
1.15 RJ45	Supply & Installation of RJ45	1.00	lot	
1.16 Cable Manager	24 P, 1 U Cable Manager	15.00	sets	
ROUGHING-IN	I INSTALLATION MATERIALS			
1.17	 Supply, installation and termination of Fiber Optic 4 core multimode outdoor type 	1.00	Lot	
1.18	 Supply, installation and termination of conduits, structured cabling 	1.00	Lot	



20 October 2023 (Friday)

DATE OF ISSUE

p.5/28

Page Number

Area 1 (Data C	installation of UTP CAT 6 Cable and Fiber Optic Cable, cable trays around the Main Conference Building, and in the side of Connecting Hallway, cable pulling, CCTV Weatherproof Conduit Boxes (100X100X70) (73 pcs), fittings, boxes, support/hangers, connectors, accessories, testing, commissioning, and decommissioning.			
•	Cabinet Installation at PABX Room)	1.00	1 -4	
	Installation of Data Cabinet with height 28U / 4 ft., Powder Coated, Black, perforated two side panels, Perforated back, and front Door; German cooling fan, with three pins German type plug, 1wire,4 fans (cable length, 1M); 1U 19" power distribution unit, w/ aluminum body, US (NEMA5-15P) Plug, 6 universal outlets, w/LED master switch at PABX Room;	1.00	Lot	
	Installation, testing, and commissioning of Two (2) Smart PoE Managed Switch, Two (2) Network Video Recorders, and Rackmount Smart-UPS power supply to the Data Cabinet;	1.00	Lot	
	Wall installation, testing, and commissioning of Two (2) 55" LED 4K Monitors connected to NVR located at PABX Room;	1.00	Lot	
	Installation of Roughing-Ins (cable trays, conduits and other necessary accessories).	1.00	Lot	
1.23	Supply, Installation, Cable Wiring Termination, Testing and Commissioning of New Electrical Panel Board with 1 pc. Main Circuit Breaker (100 Amperes) Bolt-On Type and 8 pcs. Branch Circuit Breakers Bolt-On Type (1 pc. 20 Amperes for the Lighting Circuits, 1 pc. 30 Amperes for the Air Conditioning Unit, 1pc. 30 Amperes for the Convenience Outlets, 1 pc. 40 Amperes for the UPS of the existing IT Network Infrastructure, 1pc. 40 Amperes or higher for the UPS of CCTV Surveillance System, other 3 pcs. 20 Amperes Circuit Breaker for Spare Provisions)	1.00	Lot	
	Lobby Electrical and Mechanical Ro	om IP C	CTV Posi	tions)



20 October 2023 (Friday)

DATE OF ISSUE

p.6/28

Page Number

1.24	Installation of Roughing-Ins (cable trays,	1.00	Lot	
2.27	conduits and other necessary	1.00	200	
	accessories)			
1.25	Installation of Two (2) units of Indoor	1.00	Lot	
	Dome IP CCTV Cameras at the			
	Mechanical Room and Electrical Room			
	Entrance;			
1.26	Wire Pulling, Laying, and Structured	1.00	Lot	
	cabling from Smart PoE Network Switch			
	at PABX room (for IP CCTV Cameras) to			
	Mechanical and Electrical Room located			
	at the Lower lobby (Camera No. 74 & 75)			
	based on Floor Plan/ Layout. (See			
	attached plan/ layout)			
Area 3 (Da	ta Cabinet Installation at Electrical roo	m locate	d at the	RFS Office)
1.27	Installation of One (1) unit Data Cabinet	1.00	Lot	
	with specifications of 600 x 450,			
	9u/1.5Ft. 90.7kg max. loading capacity),			
	toughed glass door w/ spring lock,			
	detachable side panel (not vented), 2			
	pcs. Exhaust fan w/ cable entry at the			
	top panel, 6 outlet PDU w/ 3.0mm cable			
	length (220V,3prong,10A), powder			
	coated finish, with exhaust fans at the Electrical room located at the RFS Office			
	area; with provision of 1KVA UPS			
	Floor/Wall Mount (4x Universal Outlets,			
	Cable Length: 1.20 mtrs, Rated Power:			
	600 Watts, HxWxD: 9.25 x 16.05 x 30.5			
	cm			
1.28	Installation, testing, and commissioning	1.00	Lot	
	of One (1) Smart PoE Managed Switch to			
	the Data Cabinet;			
1.29	Installation of Roughing-Ins (cable trays,	1.00	Lot	
	conduits and other necessary			
	accessories).			
Area 4 (Da	ta Cabinet Installation at Electrical roo	m locate	d at the	Workshop Area)
1.30	Installation of One (1) unit Data Cabinet	1.00	Lot	
	with specifications of 600 x 450,			
	9u/1.5Ft. 90.7kg max. loading capacity),			
	toughed glass door w/ spring lock,			
	detachable side panel (not vented), 2			
	pcs. Exhaust fan w/ cable entry at the			
	top panel, 6 outlet PDU w/ 3.0mm cable			
	length (220V,3prong,10A), powder			
	coated finish, with exhaust fans at the			
	Electrical room located at the Workshop			
	Area; with provision of 1KVA UPS			
	Floor/Wall Mount (4x Universal Outlets,			
	Cable Length: 1.20 mtrs, Rated Power:			
	600 Watts, HxWxD: 9.25 x 16.05 x 30.5		I	I



20 October 2023 (Friday)

DATE OF ISSUE

p.7/28

Page Number

	 									
	cm									
1.31	Installation, testing, and commissioning	1.00	Lot							
	of One (1) Smart PoE Managed Switch to									
	the Data Cabinet.									
Area 5 (Dining	g and Basement Left-wing and Right	-wing ar	ea, Engir	neering and						
Parking area IP CCTV Positions)										
1.32	Installation of Roughing-Ins (cable trays,	1.00	Lot							
	conduits and other necessary									
	accessories);									
1.33	Installation of Seventeen (17) units of	1.00	Lot							
	Indoor Dome IP CCTV Cameras and Eight									
	(8) Outdoor Bullet IP CCTV Cameras;									
1.34	Wire Pulling, Laying, and Structured	1.00	Lot							
	cabling from Smart PoE Network Switch									
	at Electrical room located at Dining									
	lobby of two (2) runs each UTP Cable (for									
	IP CCTV Cameras) to Dining Area (No. 70,									
	47, 48, 49, 71, 46, 53, 68, 54), and to									
	Basement Area (No. 45, 44, 43, 42, 40,									
	61,41) based on Floor Plan/ Layout. (See									
	attached plan/ layout);									
1.35	Another Wire Pulling, Laying, and	1.00	Lot							
	Structured cabling from Smart POE									
	Network Switch at Electrical room									
	located at Dining lobby of two (2) runs									
	each UTP Cable (for IP CCTV Cameras) to									
	Engineering, Staff lounge and Side									
	Parking area (No. 55, 56, 59, 69, 72, 73,									
	76, 77, 78) based on Floor Plan/ Layout.									
	(See attached plan/ layout);									
1.36	Conduction of Wire Termination/s along	1.00	Lot							
	with appropriate Testing &									
	Commissioning and De-commissioning									
	of old wires and hardware.									
Area 6 (2nd-fl	oor and 3rd floor Left-wing and Rigl	nt-wing I	P CCTV I	Positions)						
1.37	Installation of Roughing-Ins (cable trays,	1.00	Lot							
	conduits and other necessary									
	accessories);									
1.38	Installation of Fifteen (15) units of	1.00	Lot							
	Indoor Dome IP CCTV Cameras;									
1.39	Wire Pulling, Laying, and Structured	1.00	Lot							
	cabling from Smart PoE Network Switch									
	at Electrical room located at Dining									
	lobby of two (2) runs each UTP Cable (for									
	IP CCTV Cameras) to 2nd floor Area (No.									
	24, 33, 34, 35, 36, 37, 38, 39), and to 3rd									
	floor Area (No. 26, 27, 28, 29, 30, 31, 32)									
	based on Floor Plan/ Layout. (See									
	attached plan/ layout);									
1.40	Conduction of Wire Termination/s along	1.00	Lot							
	<u> </u>									



20 October 2023 (Friday)

DATE OF ISSUE

p.8/28

Page Number

	with appropriate Testing &			
	Commissioning and De-commissioning			
	of old wires and hardware.			
Area 7a (Upp	er Lobby and Function Room Area If	CCTV P	ositions)	
1.41	Installation of Roughing-Ins (cable trays,	1.00	Lot	
	conduits and other necessary			
	accessories);			
1.42	Installation of Thirteen (13) units of	1.00	Lot	
	Indoor Dome IP CCTV Cameras and Five			
	(5) Outdoor Bullet IP CCTV Cameras;			
1.43	Wire Pulling, Laying, and Structured	1.00	Lot	
	cabling from Smart PoE Network Switch			
	at Electrical room located in front of			
	Workshop Male CR of two (2) runs each			
	UTP Cable (for IP CCTV Cameras) to			
	Upper lobby and Function room Area			
	(No.1, 9, 10, 11, 12, 13, 14, 15, 16, 17,			
	18, 19, 20, 21, 22, 23, 25, 52) based on			
	Floor Plan/ Layout. (See attached plan/			
	layout);			
1.44	Conduction of Wire Termination/s along	1.00	Lot	
	with appropriate Testing &			
	Commissioning and De-commissioning			
	of old wires and hardware.			
Area 7b (Upp	er Lobby and Function Room Area II	P CCTV P	ositions)	
1.45	Installation of Roughing-Ins (cable trays,	1.00	Lot	
	conduits and other necessary	2.55		
	accessories):			
1.46	Installation of Two (2) units of Indoor	1.00	Lot	
2.10	Dome IP CCTV Cameras and Two (2)	2.00		
	Outdoor Bullet IP CCTV Cameras;			
1.47	Wire Pulling, Laying, and Structured	1.00	Lot	
2.17	cabling from Smart PoE Network Switch	1.00		
	located at PABX of two (2) runs each UTP			
	Cable (for IP CCTV Cameras) to Upper			
	lobby and Function room Area (No.7, 8,			
	50, 51) based on Floor Plan/ Layout. (See			
	attached plan/ layout);			
1.48	Conduction of Wire Termination/s along	1.00	Lot	
1.40	with appropriate Testing &	1.00	Loc	
	Commissioning.			
Area 0 /1 avea		TV Dooiti	one)	
	r Lobby and Side Parking Area IP CC			
1.49	Installation of Roughing-Ins (cable trays,	1.00	Lot	
	conduits and other necessary			
	accessories);			
1.50	Installation of Five (5) units of Indoor	1.00	Lot	
	Dome IP CCTV Cameras and Four (4)			
	Outdoor Bullet IP CCTV Cameras;			
1.51	Wire Pulling, Laying, and Structured	1.00	Lot	
	cabling from Smart PoE Network Switch			



20 October 2023 (Friday)

DATE OF ISSUE

p.9/28

Page Number

	located at PABX of two (2) runs each UTP Cable (for IP CCTV Cameras) to Upper lobby and Function room Area (No.2, 3, 4, 5, 6, 57, 58, 60, 62) based on Floor Plan/ Layout. (See attached plan/layout);			
1.52	Conduction of Wire Termination/s along with appropriate Testing & Commissioning.	1.00	Lot	
General Requ	uirements			
1.53	Mobilization of Manpower, equipment, tools, and temporary facilities. Provide temporary field office with health/safety/first aid facility and utilities with corresponding sub-meters to be connected to sub-meters to be connected to supply of water and electricity. Provide Personal Protective Equipment (PPE) and other Safety &	1.00	Lot	
1.54	Health Paraphernalia. Obtain building permits, and other necessary permits such as Electronic and/or Electrical Permits as required for the project;	1.00	Lot	
1.55	Supply and deliver all devices needed to install the upgraded CCTV System such as but not limited to: IP CCTV Cameras, Network Video Recorder, Wires and Cables, Data Switches, Monitors, Hard Disk Drives, etc.;	1.00	Lot	
1.56	Install piping, structured cabling, cable trays, hangers, base mountings, cabinets, accessories, CCTV devices such as cameras and video recorder, etc. in accordance to correct engineering standards and material specifications as cited in its operating manual;	1.00	Lot	
Turn-Over an	d Acceptance			
1.57	End to End Termination, Testing including Fluke testing and Optimal Time-Domain Reflectometer (OTDR) & Commissioning, Fiber Optics, Networking, Fiber Optic Cable Design, and Installation, Fiber Termination and Fusion Splicing (FOC Fusion Machine), FOC Patch Panel Splicing, and Termination, Continuity Testing Power source and Light Meters Configuration, Installation / termination and adjustment, and Programming, Decommissioning and Turn-over of all	1.00	Lot	



20 October 2023 (Friday)

DATE OF ISSUE

p.10/28

Page Number

	identified obsolete CCTV Cameras, Cablings, and other accessories, and system integration and configuration of existing CCTV System at Cottages (via internet/data connection) for the entire IP CCTV system. Repair of three (3) identified CCTV units at Cottages. Supply and installation of 4+2 100 Mbps Long-Range PoE Switch (Model: WI-PS205H).			
1.58	Clean and restore the areas affected during and after the installation and testing including rectification/correction of punch-listed items;	1.00	Lot	
1.59	Demobilization. Dismantling of temporary facilities, pullout of debris resulting from the conduct of the works	1.00	Lot	
1.60	The Contractor/Supplier shall provide a quarterly preventive maintenance checkup, free of charge for at least one year after the system has been commissioned and accepted by DAP;	1.00	Lot	
1.61	Submission of Post Documentary requirements: Original Copy of "Record Drawings/Plans" complete with legend, technical specifications, and measurements; Compilation of Periodic Project Reports including photo documentations before, during, and after implementation works. Each photo-documentation should have the date and time stamps, in jpgformat; As-Built Plans: Six (6) set of original copy in 30" x 40" sheets (drawn on a mylar sheets) signed and sealed by appropriate professional and/or engineers; Six (6) sets of blue print copies in 30" x 40" sheets signed and sealed by appropriate professional architects and engineers; and Complete set of electronic files in USB Thumb Drive of "AS-BUILT PLANS" in PDF and CAD format.	1.00	Lot	



20 October 2023 (Friday)

DATE OF ISSUE

p.11/28

Page Number

Manuals of all supplied and installed equipment comprising the Technical Specifications and Product Installation Instructions; Operational Brochure/s; Maintenance Manuals, including draft of Process and Work Instruction Manual (PAWIM) for the use of DAPCC Maintenance Personnel; Conduct training of the DAP maintenance personnel who will operate and maintain all equipment, facilities and utilities installed; and		
to the GCC Clause 5 Warranty under Section V Special Conditions of Contract		



20 October 2023 (Friday)

DATE OF ISSUE

p.12/28

PAGE NUMBER

nd development academy of the philippines

DAPCC PROPOSED CCTV LOCATION, VIEW AND NUMBER

Revised as of May 23, 2025

П				Nature of Action				
	Location	Ares (based on Floor Plan)	Description of View	(External General Ser Lityrook) Martin	Motors	Non-Lauren Jahlfebreit	(for opprode 8 mathematic	Remarks
1	Main Date / Quard House	Upper	Mein gate, guard house, & LBP ATM. Camera should have capability to zoom in with high-ces.	1			Any nullet	
I	Lower Lobby Driveway	Lower	Driveway, Incoming vehicle/s.	1			-free trubet	
3	Lower Lobby 1 Entrance	Lower	Lower lobby stairs & Audi Main Door.	1			-Imp dome	
4	Linwer Linbby 2 Entrance	Linwer	Lower lobby, & entrance. Camera at Lower Lobby Share.			- 1	- Artigo d'armire	
ì	Auditorium 1	Lower	Floor area & stage. Upgrade the comers to wide-angle.	1	-		-fing dame	
	Auditorium 2 (Stage - Left Side)	Lower	Main floor, main entrance, & side emergency east, Camera unit is at the left side of the stage.			1	4mp mone	
2	Auditorium 3 (flakony 1)	Upper	Belcong area. Camera unit will be mounted at the Ladies. Comfort Room located at Belcony area.			1	Frey Bullet	
	Auditorium 4 (Balcony Z)	Opper	Belong area. Camera unit will be mounted at the entrance.			.1	-limp burket	
¥	Front Office	Upper	Upgrade the camera to wide-angle camera.	1	-		fine dame	
i	Upper Lobby 1 (Entrance P.A. Side)	Upper	Upper lobby FA quarter left side, stains from Auditorium & Upper Lobby Men Entrance	1			-Imp dame	
1	Upper Lobby 2 (Right Side)	Upper	Upper tobby right side - Preyer room area.	1			-fing stome	
ш	Upper Latrby 5 (DAP Shop correct side)	Upper	Upper labby corner of DAP Shop			1	Amp dome	
19	Upper Lobby 4 (Right Side Entrance)	Upper	Incoming people passing through the 5 curve, and auditorium stage emergency exit.			1	-frap trulies	
14	Pathway minide/Side of conference 5-8	Upper	Pathway going to the 5-curve pathway. Camera unit to be installed near the CK women side.			1	-Imp trute)	
tá	Workshop Area (Dutoide)	Оррые	Camera Unit will be installed new Women CR at Workshop area			i	-Imp bullet	
4	Cottage flotunda	Upper	Cottage 7-9 returned & LPG area. Centers will be installed at the lower back wall of Conference area.			1	firm bullet	
7	Workshop Halfway (Male CR Side)	Upper	Hafway from workshop main CK.	1		7.	-frap dame	
ı	Workshop Hallway (Fernale CR Side)	Ugper	Hallway from workshop female CR.	1			4mp dome	
18	Contenuos I -4 Hallway	Upper	Conference 1 to 4 hallway & parity include the door entrances.	1			-Іпр дате	
12	Conference 4 - 1 Hallway	Оррыг	Conference 4 to 1 halfway & partly include the door entrances.	1			-Ing dame	
1	Admin Hallway	Upper	Office's (Cashier, ORD), & DSS) hallway and door entrances.	1			frep dame	
2	CIP to Conference 5 Hallway	Upper	Plainway infront of GP, FMSD, Contenues II to 5.	1		7	-frag dame	
1	Conf 5-8 Hallway	Upper	Hallway infront of Conference 5 to OP.	1			-fing gome	
14	Connecting Halfway 1	2nd & 3nd Fibor	Connecting heliway from Quest blidg to Upper Lobby, Includes the glass doors fronting flanteque Plaza fl.	1			-Imp truttet	
13	Connecting Hallway 3	Оррег	Connecting heliway from Upper Liabity to Guest bidg, Includes the stairway going to roof deck.			i	-Imparame	



20 October 2023 (Friday)

DATE OF ISSUE

p.13/28

PAGE NUMBER



or development academy of the philippines

DAPCC PROPOSED CCTV LOCATION, VIEW AND NUMBER

Revised as of May 23, 2025

Т		100000000000000000000000000000000000000		Nature of Action		On the second		
	Location	Area (based on Floor Plan)	Description of View (fixe		Manage	Sea Louisian January	(Interest Spe. (Interest of A statement)	Remarks
18	3 rd Floor Emergency Exit, Left Wing	2nd & 3rd Floor	Left hallway emergency sait staitway	-1			Amp dame	
17	3 rd Floor Left Wing Hwilway 1	2nd & 3rd Floor	Left Hellway from water station, Housekeeping room, 320 to 536.	1			Ampi dame	
111	3 rd Fictor Left Wing Hallway 2	2nd & 3nd Floor	Left hallway from water station, Housekeeping room 336 to 320.	1			The day	
I II	3 th Floor Right Wing Hellway 1	2nd & 3rd Floor	Right hallway from Room 301 to 318.	1			Attai d'antir	
12	3 Floor flight Wing Hellway 2	2nd & 3nd Floor	Right hallway from Room 318 to 301.	1			-three alarme	
i	3 rd Floor Emergency Exit, flight Wing	2nd & 3rd Floor	Right hallway emergency exit stainway.	1			-Timp manip	
ш	3rd Floor Middle, Lobby	2nd & 3rd Floor	3rd Roor Main lobby pointing to the stairs.			1	Firty diame	
	3 rd Floor Left Wing Hallway 1	2nd & 3rd Floor	Left hallway from water station, NFS office to room 236.	1			Attacome	
14	2 rd Floor Left Wing Hallway 2	2nd & 3rd Floor	Left hallowy from 236 to water station and RFS Office.	1			Any dance	
1	2 rd Floor Right Wing Hallway 1	2nd & 3rd Floor	Right hallway from floom 201 to 218.	1			-Time morne	
	2 rd Floor Right Wing Hallway 2	2nd & 3rd Floor	Right hallway from Room 218 to 201.	1			-time drame	
		2nd & 3rd Floor		1			Ama dame	
	2 rd Floor Emergency Exit (Left Wing)	2nd & 3rd Floor	Left hallway emergency self stairway.	1			- drags attention	
+	2 rd Roor Emergency Exit (Right Wing)	2010 86 3010 1-0009	Right hallway emergency soft stainway.	-	_	_	- such marite.	
10	2 rd Floor Middle, Listby	2nd & 3rd Floor	2nd Risor lobby stains from connecting fullway, & dming Risor.	(1)			- Angrahama	
12	Basement 1 (101 - 106)	Savement & Disting	Haltway from 101-106. Carners will be installed near 101.			1	fing dame.	
i.	Basement 2 Emergency Exit 106 - 101	Basement & Dining	Emergency sait at Sesement Hallway 100 - 101.	1		747	4hyratome	
12	Basement, 5 Lobiby Right Conver	Basement & Dining	Clarer room & lobby. Carriers will be installed at the Right Conner of Sesement Libby.	1			Ampi dome	
п	Beserrand 4 Left Wing 207 - 118	Bauamani & Dining	Linem area & stockroom door. Hallway room: 107 to 116.	1			Firty storie	
н	Basement 5 Left Wing 118 - 107	Sauement & Diving	From Clinic area. Hallway room from 118 - 107			1	-time dome.	
	Basement 6 (Ciroc Area)	Savement & Desing	Clinic entrance and heliusy going basement.	1			4mp dome	
	Dining A inside	Basement & Dining	Dining A area, Camera Imballed near the RES office.	1			4mp dome	
17	Dining If Workshop 5 Side	Basement & Disting	Dining 8 floor area. Camera installed near workshop %			1	4mp done	
41	Dining & Main Entrance	Salement & Diving	Dining 8 floor area to Workshop 3. Comera will be installed near the Dining B main entrance.	1			4mp dame	
41	Dining Listby	Swament & Dining	Waiter's country table, stairs going up to dorm area, CR entrance, Dining A area entrance.	1			Amp dame	
	Barbeque Plaza E (Right)	Upper	Berbeque Plaza S right side. Connecting hidway steps, mechanical room outdoor entrance, and glass panels of art gallery. Camera will be installed at the side of guest room wing.			30	-frequirement	
10	Barbeque Plaza B (Left)	Upper	Berbeque Plaza B Left side. Camera will be installed at the side of Art Gallery, PASX, positing at Dorm building and Desig 5 Side			1	-Trays Audier	
12	Barbeque Place A	Upper	Back of conference 4 to dining A side entrance. Camera will be installed at the side of Conference Room 4.			1	-frug itulier	
33	Kitchen Entry Front	Savement & Dining	Side entrance (Bisque Plata A side).	1			Amp puller	



2023 (Friday)

DATE OF ISSUE

20 October

p.14/28

PAGE NUMBER

new development academy of the philippines

DAPCC PROPOSED CCTV LOCATION, VIEW AND NUMBER

Revised as of May 23, 2023

1		The same of the sa		Nature of Action	100			
l	Location	Area (based on Floor Flan)	Description of View	(facetrag) Common for Linguists/ Highless	-	September (additional)	(Structure)	Remarks
Ī	Kitchen Stocknoom Area	Basement & Dining	Stockroom area hallway & entranses.			1	-feny diamer	
ľ	Staff Lounge Area	Lower	Staff lounge & drivingsy. Camera should be wide angled.	1		-	Herry trusted	
	DMS Office & Writing Rosefulde	Lower	Road from EMS office, & DAPCC car parking area.	1.0			Henry detailed	
ľ	Parking A - Near Cate 2	Leswer	Cerners will be installed at Street light post pointing at Side Parking Area			1	-Amp Audet	
	Parking B - Near Date 2	Lower	Carriers will be installed at Street light post pointing at DAPCC front parking			1	-first build	
	Parking C - Near Clinic	Lower	Carriers to be upgraded to 4mp bullet type pointing at Mutproycle Parking.				-timp trulier	
Ī	Parking D - Near Clinic	Lower	Carriers to be installed at Wall post pointing at Side Parking.			1	-firigi Assist	
ľ	Dym	Basement & Dining	Floor area of gym & entranses.			1	-time atomic	
ĺ	Cashier	Lower	Imade new cashier's office, previously flusiness Center			1	-timp atomi-	
	Callery Hallowy	Lower	Hallway & entrance of gallery, entrance of IT room & PARK.		1.		T d	to be mandained
ľ	Dallery Iroide 1	Lower	National Artist Collection area		1			to be maintained
ľ	Callery Iroide 2	Larwer	Clailery middle area side A		- 3			to be maintained
ľ	Gallery Iroide 3	Lower	Callery middle area side 5		1			to be maintained
ľ	PABX	Lower	Floor area of PASX room & critical Installations.		1			to be maintained
ľ	Kitchen Imide	Basement & Dining	Main Kitchen Area	1		-	-Originalisme	
	Driveway @ Engineering Office Area	Lower	Carners will be place @ the Engineering office pointing the driveway for incoming deliveries.	1			Grape described	
	Emergency exit beside Workshop 5	Bayerrant & Dining	Carriera will be placed @ the side of Workshop 3/ Emergency ent.				-first dame	
I	Dinning A Entrance	Deserment & Direing	Carriana will be installed near the Dining A main entrance.			1	-timp atomic	
t	Staff Lounge Invite	Lower	Carriera is installed inside the Staff Lounge	100			- First dame	
Ī	EMS Workstation (Generator Area)	Lower	Carriers will be installed mode EMS Workstation pointing to the OwnSet.			1	-Amp Audet	
	Electrical Room (Lower Lobity)	Lower (Mech. & Elect. Rejorn)	Carmers will be installed inside Electrical room at Lower Labby area			1	-first build	
	Mechanical Room (Lineer Lobby)	Lower (Mech. & Dect. Room)	Carriera will be installed milde Mechanical room at Lower Lobby area				-timpropulari	
ľ	Sewage Treatment Plant (STP)	Lower	Carriers will be installed at Utility Center painting at STP.			1.	desp builtet	
ľ	Utility Center near Engineering Building	Lower	Carnera with be installed at the Utility Center area.			1	Henry desiled	
ľ	Engineering Workshop area	Lower	Certiers will be instaffed at Engineering workshop area.	3		1	-timp auder	
	Front Parking Driveway (Main Gale)	Cottage Area	Carriera installed at Landbark ATM (Main Oats) pointing at Front Parking/Flag pole	-	- 1			to be mainteined
	Cottage Drivewey	Cottage Area	Carriera Installed of Landbank ATM pointing at Cottage Driveway	· 1	1		0 3	to be municiped
	Cottage 5	Cuttage Area	Carriera installed of Cottage 5 pointing at Rotunda		1		m V	to be maintained
	Cottage 1 (Buck Arms)	Cuttage Area	Carmers installed at the back of Cottage 1 pointing at perimeter fence and Oreentouse		. 1		10 3	to be myntained
I	Cottage 2 (Seck Area)	Cuttage Area	Carriers installed at the back of Cottage 1 pointing at perimeter fence and back of Cottage 2		1			to be maintained



20 October 2023 (Friday)

DATE OF ISSUE

p.15/28

PAGE NUMBER



nd development academy of the philippines

DAPCC PROPOSED CCTV LOCATION, VIEW AND NUMBER

Revised as of May 25, 2025

				Natu	re of Ac	tion		
	Location	Aren (based on Floor Plan)	Description of View	(Daning Commo for Engrade) Applica	Acres	Revisioner (self-real	Chewo Type (fir-seprete il alditanti)	Remarks
	Cottage 3 [Back Area)	Cottage Area	Carriers installed at the back of Cottage 5 pointing at the back of Cottage 4 and Cottage Electrical and Data Room area.		x			to be maintained
	Housekeeping Storage Room	Cottage Area	Camera installed at the side of Houskeeping storage room well pointing at the tack of Cottage II and VIIIs area.		i			to be maintained
	Cottage II (Back Area)	Cottage Area	Carriera installed at the back of Cottage 9 pointing at F85 ramp and LPG area	-00.00	1			to be maintained.
ĺ			Total	41	13	32		80

total no. of cameras

Type of Camera to be Purchased	No. of Cameras
4mp Bullet Type Camera	26
4mp Dome Type Camera	47
Total No. of Cameres to be purchased:	73
No. of Cameras to be Maintained:	13

AREAS:	No, of Cameras			
Upper	22			
Lower	23			
Lower (Mech. & Elect. Room)	2			
Basement & Dining	10			
2nd & 3rd Floor	15			




20 October 2023 (Friday)

DATE OF ISSUE

p.16/28

PAGE NUMBER





Annex "A" – Revised Technical Specifications

20 October 2023 (Friday)

DATE OF ISSUE


p.17/28

PAGE NUMBER





20 October 2023 (Friday) PAGE NUMBER p.18/28






Annex "A" - Revised Technical Specifications

20 October 2023 (Friday)

DATE OF ISSUE

p.19/28

PAGE NUMBER






Annex "A" - Revised Technical Specifications

(AS PER BID BULLETIN No.1)

20 October 2023 (Friday)

PAGE NUMBER

p.20/28






Annex "A" - Revised Technical Specifications

20 October 2023 (Friday)

DATE OF ISSUE

p.21/28

PAGE NUMBER






2023 (Friday)

20 October

DATE OF ISSUE

p.22/28

PAGE NUMBER






Annex "A" - Revised Technical Specifications

20 October 2023 (Friday)

DATE OF ISSUE

p.23/28


PAGE NUMBER





Annex "A" - Revised Technical Specifications

 DATE OF ISSUE	Page Number
20 October 2023 (Friday)	p.24/28





ANNEX "A" - REVISED TECHNICAL SPECIFICATIONS

20 October 2023 (Friday) p.25/28

PAGE NUMBER

DATE OF ISSUE

(AS PER BID BULLETIN No.1)

LEGEND: DALERY DALLERY BULLET CAMERA RECOMBIGUE ARROWAL BY SOLECT THE ##15 PT WHOSE SF 19427 (1945) GEST NO development academy of the EECHOL HOW INC. HOW philippines SWICE OCT SURVEILLANCE. SERSTINE VEH B. SECURICA ALDERTO AVICELO M. AMENEZ PACHESA L. DOCELLO MINERO 7 13 IN THE SELECT SECURITY OF



Annex "A" - Revised Technical Specifications

2023 (Friday)

DATE OF ISSUE

20 October

p.26/28

PAGE NUMBER

(AS PER BID BULLETIN No.1)

DEEPWELL PLANE LEGEND: LEARNING AND LEISURE PAINT NETWORK SWITCH CABLE TRAY SOURT THE CENCH BY HELOMENING APPROVE BY APPROVED BY THEFT CONTENT SHEET NO. development academy of the REPORT CARE THE AT WAS ELECTION. SWEEN STATES philippines MONNA AR DE ARNAS DHISTWA VER B, SIGUENZA ALBERTO ANCELO M. AMENEJ PAG-ASA L. DOGEJA 10 13 DE CHESTO DATE INVESTOR OF



Annex "A" - Revised Technical Specifications

20 October 2023 (Friday)

DATE OF ISSUE

p.27/28

PAGE NUMBER

(AS PER BID BULLETIN No.1)



2nd Floor Lobby to EE Room

3rd Floor Lebby

Basement Lobby to EE Room,& Hallway



Back of 3rd Floor Lobby

PABX, Cashier,& Front Office

Connecting Hallway



development academy of the philippines

FRANCE TREE	0000 W	HEISMEING KYRNAL (K.		AMIND III	3407 CH004	1807 16
DATE OF STREETWOE	CHICAN VOI II OCHOUR	AUDIO INCELO M. IMPAC	790-453 L 000000	MINNS AN DE ATRICS	HARDS DATE THE /	12 13



ANNEX "A" - REVISED TECHNICAL SPECIFICATIONS

(AS PER BID BULLETIN No.1)

DATE OF ISSUE PAGE NUMBER

20 October 2023 (Friday)

p.28/28



Main Electrical Room,& PABX Room

Main Electrical Room

Back of Conference Rm 5-8, FMSO. OP



Back of Conference Rm 5-8, FMSO, & OP



Back of FCIL, Workshop 4A, Clinic,& PMDP Office



Back of 2nd Floor Lobby, & Room 201



Back of 2nd,3rd Floors Lobby,& Rms 201,301



development academy of the philippines

AUL KROW RESIDENCE ATTECHA DE (ESON OF INTER CITY SOMBLACK SAL THE BASE SHEET, ROWSE ST

CHRISTIAN VER R. SIDJENZA ALIENTO ANCELO W JAMENEZ PANI-ANA L. DORDO

WOMING AR DE ARMOR

4095004ED BY

PERSONAL CHEET THAT /

9-KET COSTEVE

13 13

DHEF NO.



(AS PER BID BULLETIN No.1) 2023 (Friday

20 October 2023 (Friday)

Page __of ___.

DATE OF ISSUE

p.1/21

PAGE NUMBER

Bidder's LETTERHEAD

FORM 2: PRICE SHEDULE

(AS PER GPPB RESOLUTION NO. 16-2020)

INSTRUCTIONS to BIDDERS:

Name of Bidder

Invitation to Bid Number:

- 01. THIS FORM SHOULD BE ACCOMPLISHED USING THE BIDDER'S LETTERHEAD, SIGNED COPY SHOULD BE SUBMITTED AS PART OF THE FINANCIAL DOCUMENTS MARKED AS "F02";
- THE SIGNED COPY OF THIS DOCUMENT (IN PDF OR JPEG FORMAT) MUST BE PART OF THE ELECTRONIC FILES THAT SHOULD BE CONTAINED IN THE SUBMITTED ELECTRONIC BID; AND
- 03. DO NOT LEAVE BLANK CELLS. KINDLY PUT N/A IF "NOT APPLICABLE";
- 04. KINDLY USE ADDITIONAL SHEETS IF NECESSARY; AND
- 05. THE FILENAME STRUCTURE SHOULD BE "FO2_XXX=PRICE_SCHEDULE=<BIDDERNAME>".

For Goods Offered From Within the Philippines

1	2	3	4	5	6	7	8	9	10
Item	Description	QTY	UNIT	Unit price EXW per item	Transportation and Insurance and all other costs incidental to delivery, per item	Sales and other taxes payable if Contract is awarded, per item	Cost of Incidental Services, if applicable, per item	Total Price, per unit (col 5+6+7+8)	Total Price delivered Final Destination (col 9) x (col 4)
HARDV	VARES								
1.01	Supply and installation	52.00	pcs	\(\frac{1}{2}\)		()		0. 12	
Dome IP Camera	of Dome IP CCTV Camera:								
	1/3 in. 4MP Progressive-scan CMOS Sensor								
	 Triple-stream Encoding 								
	Smart H.265+ and Smart H.264+ Dual Codec								
	4MP (2688 × 1520) @30 fps, 2.8, Fixed Lens								
	Starlight Technology for Low-light Applications								
	Analytics+ Function —Perimeter Protection and Smart Motion Detection								



20 October 2023 (Friday)

DATE OF ISSUE

p.2/21

PAGE NUMBER

(AS PER BID BULLETIN No.1)

True Wide Dynamic Range (120 dB) and Day/Night IR Cut Filter Enhanced Power and Data Transmission Distances (ePoE) Arctic Pro Series Camera Operational down to -40deg C(-40deg IP67 Ingress Protection and IK10 Vandal Resistance with Warranty 1.02 Supply and installation 21.00 pcs Bullet IP of Bullet IP CCTV Camera Camera: 5MP (2592 × 1944) @20 fps, 1/2.7"" image sensor, 24/7 Full-color image SMART H.264+/H.265+, AI H.264/H.265 encoding 2.8/3.6 mm fixed lens · Built-in warm light and IR LED; the max. IR illumination distance is 30m Smart Dual Illumination Active Deterrence: Sound and light alarm Support vehicle and human classification Intelligent detection: Intrusion, tripwire



20 October 2023 (Friday)

DATE OF ISSUE

p.3/21

Page Number

	 12V DC/PoE power supply IP67 protection with Warranty 					
1.03 Smart POE Unmana ged Data Switch	Supply and installation of 24 port Smart POE Unmanaged Data Switch:		pcs			
1.04 64 Channel Network	Supply and installation of Two (2) 64 Channel	2.00	pcs	Ú.		



20 October 2023 (Friday)

DATE OF ISSUE

p.4/21

Page Number

Video	Network Video						
Recorder	Recorder: Smart H.265+/Smart H.264+/H.265/H.26 4 support 64-ch IPC inputs, max resolution 12MP 320Mbps input Bandwidth						
	Support 16-ch 1080p@30 fps self- adaptive decoding ability 8 SATA III ports, up						
	to 10 TB for a single HDD • 2 VGA, 2 HDMI, 2						
	RJ45(1000M) Supports ONVIF protocol, DHCP, P2P function						
	1-channel fisheye dewarping (AI by NVR)						
	 Al by Camera: Perimeter protection; face detection and recognition; SMD 						
	Plus; video metadata; ANPR; people counting; heat map • with Warranty					ý	
1.05 Data Cabinet	Supply and installation of Data Cabinet: • Data Cabinet will be install at the following areas: ✓ PABX Room (28U / 4 feet Data Cabinet);	4.00	pcs				



20 October 2023 (Friday)

DATE OF ISSUE

p.5/21

PAGE NUMBER

	Door with Lock; Detachable Side Panels with Lock & Ventilation; Detachable Back Panels with Lock; With 1 unit Vertical powerstrip 4 CO's, 3 prong, 220V, 20 Amp fuse; With 1 unit Vertical Cable Manager at the back ring type; and with 4 pcs. Exhaust								
		2 0	1000000	2	8	8	9	No.	
10TB Hard	10TB Surveillance Hard Disk Drive SATA III; with Warranty	1-12-11-11-1	pcs						



20 October 2023 (Friday)

DATE OF ISSUE

p.6/21

PAGE NUMBER

(AS PER BID BULLETIN No.1)

Patch LC 12mm/18mm Cable with Short Boots; End to SC 25mm with End Short Boots (300M) · Polish Type SMF: UPC-UPC; UPC-APC; APC-APC; UPC-UPC MMF: Connector Ferrule Zirconia Ceramic Cable Outside Diameter Duplex: 1.6/2.0/3.0mm, Simplex: 0.9/2.0/3.0mm, Interchangeability ≤0.2dB, Vibration ≤0.2dB with Warranty 1.08 Single mode single 6.00 pcs Fiber fiber; LC port; Optical 1310nm sending, Module and 1550nm receiving; Transmission distance up to 20km; with Warranty 1.09 55" 55" 4K UHD LED 2.00 pcs LED 4K Monitor; Monitor Industrial level LCD panel, suitable for continuous 24/7 operation • 4K Ultra-HD resolution Using tamper-proof metal housing Built-in 3D COMB filter and 3D noise reduction 6ms response time for no motion blur or ghosting



(AS PER BID BULLETIN No.1) 2023 (Fri

20 October 2023 (Friday) PAGE NUMBER p.7/21

	1.07G colors, for a realistic and immersive visual experience High-fidelity digital processing 178°/178° wide uninterrupted viewing angle With Bracket with Warranty		2 - 3			
1.10 Fiber Patch Panel	 Category 6 180° 1U 24-Port Unshielded Patch Panel, Dual Type IDC, W/ Two Cable Management Bars, Black; with Warranty 		pcs			
1.11 Fiber Patch Cord	LC/UPC - SC/UPC Duplex Single mode, 9/125 Patch Cord 2M,2.0mm, LSOH; with Warranty		pcs			
1.12 UTP CAT6 Cable	Supply & Installation of Universal Twisted Pair (UTP) Category 6 (CAT 6) Cable, 305 meter or 1000 ft. per box; with Warranty		lot			
1.13 LC Pigtail	Multimode OM3 Simples 1M, 4.0 mm, LSOH; with Warranty	25.00	pcs			
1.14 Smart- UPS Power Supply	 Supply & Installation of High frequency, On-line Smart UPS, Rack- Tower Convertible, Hot-Swappable Battery Module Design, 		pc			



20 October 2023 (Friday)

DATE OF ISSUE

p.8/21

PAGE NUMBER

(AS PER BID BULLETIN No.1)

 3KVA/2.7 KW, PF: 0.9, 72Vdc, with 6pcs X 9Ah built-in battery, with USB, RS232, EPO, SNMP function Port with Warranty 1.15 Supply & Installation of 1.00 lot **RJ45** 24 P, 1 U Cable 15.00 1.16 Cable Manager Manager **ROUGHING-IN INSTALLATION MATERIALS** 1.17 Supply, installation and 1.00 termination of Fiber Optic 4 core multimode outdoor type 1.18 Supply, installation and 1.00 Lot termination conduits, structured cabling installation of UTP CAT 6 Cable and Fiber Optic Cable, cable trays around the Main Conference Building, and in the side of Connecting Hallway, cable pulling, CCTV Weatherproof Conduit Boxes (100X100X70) (73 pcs), fittings, boxes, support/hangers, connectors. accessories, testing, commissioning, and decommissioning. Area 1 (Data Cabinet Installation at PABX Room) 1.19 Installation of Data 1.00 Lot Cabinet with height 28U / 4 ft., Powder Coated, Black, perforated two side panels, Perforated back, and front Door;



2: PRICE SCHEDULE 2023 (Frida 2023 (Frida

20 October 2023 (Friday)

DATE OF ISSUE

p.9/21

Page Number

	German cooling fan,			7)	É	Ď.			
	with three pins German	1							
	type plug, 1wire,4 fans								
	(cable length, 1M); 1U								
	19" power distribution								
	unit, w/ aluminum								
	body, US (NEMA5-15P)								
	Plug, 6 universal	l .							
	outlets, w/LED master								
rintelectors	switch at PABX Room;	V Services	10 / 2004	0	2	0			
1.20	Installation, testing,		Lot						
	and commissioning of								
	Two (2) Smart PoE								
	Managed Switch, Two								
	(2) Network Video								
	Recorders, and								
	Rackmount Smart-UPS								
	power supply to the								
	Data Cabinet;								
1.21	Wall installation,	1 00	Lot	7		0 0			
	testing, and		1.555						
	commissioning of Two								
	(2) 55" LED 4K Monitors								
	connected to NVR								
	located at PABX Room;								
1.22		1.00	Lot	š		0 -		8	
1.22			Lot						
	Roughing-Ins (cable	1							
	trays, conduits and								
	other necessary								
1000000	accessories).	-	3	4		4 1			
1.23	Supply, Installation,	787,72,56	Lot						
	Cable Wiring								
	Termination, Testing								
	and Commissioning of								
	New Electrical Panel								
	Board with 1 pc. Main								
	Circuit Breaker (100								
	Amperes) Bolt-On Type								
	and 8 pcs. Branch								
	Circuit Breakers Bolt-On								
	Type (1 pc. 20 Amperes								
	for the Lighting Circuits,								
	1 pc. 30 Amperes for								
	the Air Conditioning						1		1



Annex "B" - Revised Form 2: PRICE SCHEDULE

(AS PER BID BULLETIN No.1)

DATE OF ISSUE Page Number 20 October 2023 (Friday)

p.10/21

	Unit, 1pc. 30 Amperes for the Convenience Outlets, 1 pc. 40 Amperes for the UPS of the existing IT Network Infrastructure, 1pc. 40 Amperes or higher for the UPS of CCTV Surveillance System, other 3 pcs. 20 Amperes Circuit Breaker for Spare Provisions)								
	(Lower Lobby Electrica			nical R	oom IP Co	TV Position	ons)	1:	12:
1.24	Installation of Roughing-Ins (cable trays, conduits and other necessary accessories)		Lot						
1.25	Installation of Two (2) units of Indoor Dome IP CCTV Cameras at the Mechanical Room and Electrical Room Entrance;		Lot		-15				
1.26	Wire Pulling, Laying, and Structured cabling from Smart PoE Network Switch at PABX room (for IP CCTV Cameras) to Mechanical and Electrical Room located at the Lower lobby (Camera No. 74 & 75) based on Floor Plan/Layout. (See attached plan/layout)		Lot						
Area 3	(Data Cabinet Installat	ion at	Electri	cal roo	m locate	d at the RF	S Office)	200	20
1.27	Installation of One (1) unit Data Cabinet with specifications of 600 x 450, 9u/1.5Ft. 90.7kg max. loading capacity),	1886 S. A.L.O.	Lot			50			



20 October 2023 (Friday)

DATE OF ISSUE

p.11/21

Page Number

	toughed glass door w/		Ť	Ì		İ		Ī	
	spring lock, detachable								
	side panel (not vented),								
	2 pcs. Exhaust fan w/								
	cable entry at the top								
	panel, 6 outlet PDU w/								
	3.0mm cable length								
	(220V,3prong,10A),								
	powder coated finish,								
	with exhaust fans at the								
	Electrical room located								
	at the RFS Office area;								
	with provision of 1KVA								
	UPS Floor/Wall Mount								
	(4x Universal Outlets,								
	Cable Length: 1.20								
	mtrs, Rated Power: 600								
	Watts, HxWxD: 9.25 x								
	16.05 x 30.5 cm								
1.28	Installation, testing,	1.00	Lot		8				S
	and commissioning of								
	One (1) Smart PoE								
	Managed Switch to the								
	Data Cabinet;								0.5
1.29	Installation of	1.00	Lot						
	Roughing-Ins (cable								
	trays, conduits and								
	other necessary								
	accessories).		100		8		2		
Area 4	(Data Cabinet Installat	ion at	Electr	ical roon	n located a	t the Wor	kshop Are	a)	
1.30	Installation of One (1)	1.00	Lot				2) 120	0.00	
	unit Data Cabinet with								
	specifications of 600 x								
	450, 9u/1.5Ft. 90.7kg								
	max. loading capacity),								
	toughed glass door w/								
	spring lock, detachable								
	side panel (not vented),								
	2 pcs. Exhaust fan w/								
	cable entry at the top								
	panel, 6 outlet PDU w/								
	3.0mm cable length								
	(220V,3prong,10A),								
	powder coated finish,		1		1	1	1	1	1



20 October 2023 (Friday)

DATE OF ISSUE

p.12/21

Page Number

	with exhaust fans at the Electrical room located at the Workshop Area; with provision of 1KVA UPS Floor/Wall Mount (4x Universal Outlets, Cable Length: 1.20 mtrs, Rated Power: 600 Watts, HxWxD: 9.25 x 16.05 x 30.5 cm	0.							
1.31	Installation, testing, and commissioning of One (1) Smart PoE Managed Switch to the Data Cabinet.		Lot						
	(Dining and Basemen	t Left-	wing a	nd Righ	t-wing a	ea, Engin	eering and	Parking a	rea IP CCTV
Position 1.32	912.9	1.00	Lot				En S		
1.33	Installation of Seventeen (17) units of Indoor Dome IP CCTV Cameras and Eight (8) Outdoor Bullet IP CCTV Cameras;		Lot						
1.34	Wire Pulling, Laying, and Structured cabling from Smart PoE Network Switch at Electrical room located at Dining lobby of two (2) runs each UTP Cable	10000	Lot						



20 October 2023 (Friday)

DATE OF ISSUE

p.13/21

Page Number

1.35	Another Wire Pulling,	1.00	Lot	77	- 4		77		×
	Laying, and Structured	I							
	cabling from Smart POE								
	Network Switch at								
	Electrical room located								
	at Dining lobby of two								
	(2) runs each UTP Cable								
	(for IP CCTV Cameras)								
	to Engineering, Staff								
	lounge and Side Parking	l							
	area (No. 55, 56, 59, 69,								
	72, 73, 76, 77, 78) based								
	on Floor Plan/ Layout.								
	(See attached plan/								
1.00	layout);	1.00	1.4				2 3		Ü
1.36	Conduction of Wire	1.00	Lot						
	Termination/s along								
	with appropriate								
	Testing &								
	Commissioning and De-								
	commissioning of old								
	wires and hardware.					AND THE PARTY OF T		,	S
Area 6	(2nd-floor and 3rd floo		_	and Right-w	ing IP CC	TV Posit	ions)		<i>(</i> *
1.37	Installation of	1.00	Lot	-					
	Deviation to Lockle			I .				1	1
	Roughing-Ins (cable								
	trays, conduits and								
3	trays, conduits and		18 - 5		g				
1.38	trays, conduits and other necessary		Lot						
1.38	trays, conduits and other necessary accessories);		Lot				g		Si .
1.38	trays, conduits and other necessary accessories); Installation of Fifteen		Lot	9	,				
1.38	trays, conduits and other necessary accessories); Installation of Fifteen (15) units of Indoor Dome IP CCTV Cameras;	1.00	Lot	2					
1000000	trays, conduits and other necessary accessories); Installation of Fifteen (15) units of Indoor Dome IP CCTV Cameras; Wire Pulling, Laying,	1.00	,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,						
	trays, conduits and other necessary accessories); Installation of Fifteen (15) units of Indoor Dome IP CCTV Cameras; Wire Pulling, Laying, and Structured cabling	1.00	,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,		,				
1000000	trays, conduits and other necessary accessories); Installation of Fifteen (15) units of Indoor Dome IP CCTV Cameras; Wire Pulling, Laying, and Structured cabling from Smart PoE	1.00	,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,	2 3					
1000000	trays, conduits and other necessary accessories); Installation of Fifteen (15) units of Indoor Dome IP CCTV Cameras; Wire Pulling, Laying, and Structured cabling from Smart PoE Network Switch at	1.00	,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,	2					
1000000	trays, conduits and other necessary accessories); Installation of Fifteen (15) units of Indoor Dome IP CCTV Cameras; Wire Pulling, Laying, and Structured cabling from Smart PoE Network Switch at Electrical room located	1.00	,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,						
1000000	trays, conduits and other necessary accessories); Installation of Fifteen (15) units of Indoor Dome IP CCTV Cameras; Wire Pulling, Laying, and Structured cabling from Smart PoE Network Switch at Electrical room located at Dining lobby of two	1.00	,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,						
1000000	trays, conduits and other necessary accessories); Installation of Fifteen (15) units of Indoor Dome IP CCTV Cameras; Wire Pulling, Laying, and Structured cabling from Smart PoE Network Switch at Electrical room located at Dining lobby of two (2) runs each UTP Cable	1.00	,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,	0					
1000000	trays, conduits and other necessary accessories); Installation of Fifteen (15) units of Indoor Dome IP CCTV Cameras; Wire Pulling, Laying, and Structured cabling from Smart PoE Network Switch at Electrical room located at Dining lobby of two (2) runs each UTP Cable (for IP CCTV Cameras)	1.00	,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,						
1000000	trays, conduits and other necessary accessories); Installation of Fifteen (15) units of Indoor Dome IP CCTV Cameras; Wire Pulling, Laying, and Structured cabling from Smart PoE Network Switch at Electrical room located at Dining lobby of two (2) runs each UTP Cable (for IP CCTV Cameras) to 2nd floor Area (No.	1.00	,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,						
1000000	trays, conduits and other necessary accessories); Installation of Fifteen (15) units of Indoor Dome IP CCTV Cameras; Wire Pulling, Laying, and Structured cabling from Smart PoE Network Switch at Electrical room located at Dining lobby of two (2) runs each UTP Cable (for IP CCTV Cameras) to 2nd floor Area (No. 24, 33, 34, 35, 36, 37,	1.00	,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,						
1000000	trays, conduits and other necessary accessories); Installation of Fifteen (15) units of Indoor Dome IP CCTV Cameras; Wire Pulling, Laying, and Structured cabling from Smart PoE Network Switch at Electrical room located at Dining lobby of two (2) runs each UTP Cable (for IP CCTV Cameras) to 2nd floor Area (No.	1.00	,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,						



20 October 2023 (Friday)

DATE OF ISSUE

p.14/21

Page Number

\ \	Floor Plan/ Layout. (See attached plan/ layout);					3		33
1.40	Conduction of Wire Termination/s along with appropriate Testing & Commissioning and Decommissioning of old wires and hardware.		Lot			3		
Area 7	a (Upper Lobby and Fu	nction	Room A	rea IP CCT	V Positi	ions)		
1.41	Installation of Roughing-Ins (cable trays, conduits and other necessary accessories);	1.00	Lot			,		
1.42	Installation of Thirteen (13) units of Indoor Dome IP CCTV Cameras and Five (5) Outdoor Bullet IP CCTV Cameras;	1.00	Lot			2		8
1.43	Wire Pulling, Laying, and Structured cabling from Smart PoE Network Switch at Electrical room located in front of Workshop Male CR of two (2) runs each UTP Cable (for IP CCTV Cameras) to Upper lobby and Function room Area (No.1, 9, 10, 11, 12, 13, 14, 15, 16, 17, 18, 19, 20, 21, 22, 23, 25, 52) based on Floor Plan/Layout. (See attached plan/layout);		Lot					
1.44	Conduction of Wire Termination/s along with appropriate Testing & Commissioning and Decommissioning of old wires and hardware.	1.00	Lot					



20 October 2023 (Friday)

DATE OF ISSUE

p.15/21

PAGE NUMBER

1.45	Installation of	1.00	Lot			,		
4.74	Roughing-Ins (cable trays, conduits and other necessary accessories);		Lot					
1.46	Installation of Two (2) units of Indoor Dome IP CCTV Cameras and Two (2) Outdoor Bullet IP CCTV Cameras;	1.00	Lot					
1.47	Wire Pulling, Laying, and Structured cabling from Smart PoE Network Switch located at PABX of two (2) runs each UTP Cable (for IP CCTV Cameras) to Upper lobby and Function room Area (No.7, 8, 50, 51) based on Floor Plan/ Layout. (See attached plan/ layout);	1.00	Lot					
1.48	Conduction of Wire Termination/s along with appropriate Testing & Commissioning.	1.00	Lot					
Area 8 (Lower Lobby and Side	Parki	ng Are	IP CCTV Positio	ns)		2	
1.49	Installation of Roughing-Ins (cable trays, conduits and other necessary accessories);	1.00	Lot	R				
1.50	Installation of Five (5) units of Indoor Dome IP CCTV Cameras and Four (4) Outdoor Bullet IP CCTV Cameras;	1.00	Lot					
1.51	Wire Pulling, Laying, and Structured cabling from Smart PoE Network Switch located	1.00	Lot					



20 October 2023 (Friday)

DATE OF ISSUE

p.16/21

Page Number

	at PABX of two (2) runs each UTP Cable (for IP CCTV Cameras) to Upper lobby and Function room Area (No.2, 3, 4, 5, 6, 57, 58, 60, 62) based on Floor Plan/ Layout. (See attached plan/layout);							
1.52	Conduction of Wire Termination/s along with appropriate Testing & Commissioning.	1.00	Lot		81		8	
Genera	al Requirements					**		
1.53	Manpower, equipment, tools, and temporary facilities. Provide temporary field office with health/safety/first aid facility and utilities with corresponding sub-meters to be connected to sub-meters to be connected to supply of water and electricity. Provide Personal Protective Equipment (PPE) and other Safety & Health Paraphernalia.	1.00	Lot					
1.54	Obtain building permits, and other necessary permits such as Electronic and/or Electrical Permits as required for the project;	0.0000000000000000000000000000000000000	Lot					
1.55	Supply and deliver all devices needed to install the upgraded CCTV System such as but not limited to: IP	1.00	Lot					



20 October 2023 (Friday)

DATE OF ISSUE

p.17/21

Page Number

	CCTV Cameras, Network Video Recorder, Wires and Cables, Data Switches, Monitors, Hard Disk Drives, etc.;				
1.56	Install piping, structured cabling, cable trays, hangers, base mountings, cabinets, accessories, CCTV devices such as cameras and video recorder, etc. in accordance to correct engineering standards and material specifications as cited in its operating manual;	Lot			
Turn-C	ver and Acceptance				
1.57	End to End Termination, Testing including Fluke testing and Optimal Time- Domain Reflectometer (OTDR) & Commissioning, Fiber Optics, Networking, Fiber Optic Cable Design, and Installation, Fiber Termination and Fusion Splicing (FOC Fusion Machine), FOC Patch Panel Splicing, and Termination, Continuity Testing Power source and Light Meters Configuration, Installation / termination and adjustment, and Programming, Decommissioning and	Lot			



20 October 2023 (Friday)

DATE OF ISSUE

p.18/21

Page Number

	identified obsolete CCTV Cameras, Cablings, and other accessories, and system integration and configuration of existing CCTV System at Cottages (via internet/data connection) for the entire IP CCTV system. Repair of three (3) identified CCTV units at Cottages. Supply and installation of 4+2 100 Mbps Long- Range PoE Switch (Model: WI-PS205H).						
1.58	Clean and restore the areas affected during and after the installation and testing including rectification/correction of punch-listed items;	1.00	Lot		3		
1.59	Demobilization. Dismantling of temporary facilities, pullout of debris resulting from the conduct of the works	1.00	Lot				
1.60	The Contractor/Supplier shall provide a quarterly preventive maintenance checkup, free of charge for at least one year after the system has been commissioned and accepted by DAP;	1.00	Lot				
1.61	Submission of Post Documentary requirements:	1.00	Lot				15



20 October 2023 (Friday)

DATE OF ISSUE

p.19/21

Page Number

Original Copy of		
"Record		
Drawings/Plans"		
complete with		
legend, technical		
specifications, and		
measurements;		
Control of the Contro		
Compilation of		
Periodic Project		
Reports including		
photo		
documentations		
before, during, and		
after		
implementation		
works. Each photo-		
documentation		
should have the		
date and time		
stamps, in jpg-		
format;		
As-Built Plans:		
✓ Six (6) set of		
original copy in		
30" x 40"		
sheets (drawn		
on a mylar		
sheets) signed		
and sealed by		
appropriate		
professional		
and/or		
engineers;		
✓ Six (6) sets of		
blue print		
copies in 30" x		
40" sheets		
signed and		
sealed by		
appropriate		
professional		
architects and		
engineers; and		
✓ Complete set of		
electronic files		



20 October 2023 (Friday)

DATE OF ISSUE

p.20/21

Page Number

	in USB Thumb		- 10	*11	
	Drive of "AS-				
	BUILT PLANS"				
	in PDF and CAD				
	format.				
•	Manuals of all				
	supplied and				
	installed				
	equipment				
	comprising the				
	Technical				
	Specifications and				
	Product Installation				
	Instructions;				
	Operational				
7-0	Brochure/s;				
1.7	Maintenance				
	Manuals, including				
	draft of Process and				
	Work Instruction				
	Manual (PAWIM)				
	for the use of				
	DAPCC				
	Maintenance				
	Personnel;				
•	Conduct training of				
1 5	the DAP				
	maintenance				
	personnel who will				
	operate and				
	maintain all				
	equipment,				
	facilities and				
	utilities installed;				
	Warranty				
	Certificate that				
	complies to the				
	GCC Clause 5				
	Warranty under				
	Section V Special				
- 1	Conditions of				
	Contract				



20 October 2023 (Friday)

DATE OF ISSUE

p.21/21

Page Number

			For G	oods Offered	From Abro	oad		
Name	of Bidder						_of	
Invitat	ion to Bid Num	ber:						
		1 2					0	
1 Item	2 Description	Country of origin	4 Quantity	Unit price CIF port of entry (specify port) or CIP named place (Specify border point or place of destination)	6 Total CIF or CIP price per item (col.4 x 5)	7 Unit Price Delivered Duty Unpaid (DDU)	8 Unit price Delivered Duty Paid (DDP)	9 Total Price delivered DDP (col.4 x 8)
Y.								
3			i i		3	63		.
Name:	Capacity:		ý g		1			



Annex "C" - SCHEDULE OF REQUIREMENTS

(AS PER BID BULLETIN No.1)

Date of ISSUE	Page Number
20 October 2023 (Friday)	p.1/1

Section VI. Schedule of Requirements

The delivery schedule expressed as weeks/months stipulates hereafter a delivery date which is the date of delivery to the project site.

Item Number	Description	Quantity	Delivered, Weeks/Months
1	IP CCTV Cameras	73 pcs	Within 60 days from receipt of NTP
2	64 Channel Network Video Recorder	2 pcs	Within 60 days from receipt of NTP
3	24-port Network Switch- Hardware	6 pcs	Within 60 days from receipt of NTP
4	Data Cabinet 9U, 12U, 28U w/built-in Fan	4 pcs	Within 60 days from receipt of NTP
5	55" LED 4K Monitor	2 pcs	Within 60 days from receipt of NTP
6	Smart-UPS Power Supply	1 pc	Within 60 days from receipt of NTP
7	Surveillance Hard Drive (10TB)	16 pcs	Within 60 days from receipt of NTP
8	Fiber Patch Cable End to end (300M)	1 roll	Within 60 days from receipt of NTP
9	Fiber Optic Module	6 pcs	Within 60 days from receipt of NTP
10	UTP CAT6 Cable	1 lot	Within 60 days from receipt of NTP
11	Fiber Patch Panel	6 pcs	Within 60 days from receipt of NTP
12	Fiber Patch Cord	80 pcs	Within 60 days from receipt of NTP
13	RJ45	1 lot	Within 60 days from receipt of NTP